

# Wheelabrator North Andover, Inc. Waste Characterization Study Report

---

Prepared for  
Wheelabrator North Andover Inc.  
285 Holt Road  
North Andover, MA 01845

Facility ID# 132771  
January 17, 2014



151 Campanelli Drive, Suite B  
Middleboro, MA 02346

# Table of Contents

List of Figures .....	ii
List of Tables .....	ii
List of Appendices .....	ii
1. Executive Summary .....	1
2. Introduction .....	1-1
1.1 Background .....	1-1
1.2 Introduction .....	1-1
3. Methodology .....	2-1
2.1 Allocation of Number of Samples by Haul Type .....	2-1
2.2 Sampling Procedure .....	2-2
2.2.1 Load Selection .....	2-2
2.2.2 Sorting Procedures .....	2-3
2.2.3 Documentation of Sample Data .....	2-3
4. Results .....	3-1
3.1 Method of Data Analysis .....	3-1
3.2 Overall Composition of Waste .....	3-1
3.3 Composition of Waste by Sampling Season .....	3-5
3.4 Composition of Waste by Sector .....	3-6
3.4.1 Residential Sector .....	3-7
3.4.2 ICI Sector .....	3-8
3.4.3 Unacceptable Loads .....	3-8
3.5 Waste Composition by Haul Type .....	3-9
3.6 Observations and Analysis .....	3-19
5. References .....	4-1
Figures .....	FIG-1
Appendix A: Description of Waste Categories .....	A-1
Appendix B: Waste Composition of Sample Loads for Season 1 .....	B-1
Appendix C: Waste Composition of Sample Loads for Season 2 .....	C-1
Appendix D: Driver Questionnaire and Field Data Sheet .....	D-1
Appendix E: Permit Approval Class II Recycling Permit .....	E-1
Appendix F: Calculation for Number of Samples .....	F-1

## List of Figures

---

Figure ES-1 Overall Waste Composition

Figure 1-1 Site Locus Map

Figure 1-2 Aerial Map

Figure 1-3 Tipping Floor Site Plan

Figure 3-1 Overall Composition of Waste

Figure 3-2 Residential Waste Composition

Figure 3-3 ICI Waste Composition

## List of Tables

---

Table ES-1 Summary of Waste Composition.....	ES-3
Table 1-1 Wheelabrator North Andover, Inc. Service Area.....	1-2
Table 2-1 Number and Allocation of Samples - Wheelabrator North Andover, Inc.....	2-2
Table 3-1 Overall Waste Composition at Wheelabrator North Andover, Inc. ....	3-3
Table 3-2 Composition of Waste by Season.....	3-5
Table 3-3 Number and Allocation of Samples by Vehicle Type.....	3-9
Table 3-4 Waste Composition of Roll-off Open Top.....	3-10
Table 3-5 Waste Composition of Roll-off Closed Top.....	3-11
Table 3-6 Waste Composition of Roll-off Compactor.....	3-13
Table 3-7 Waste Composition of Rear Loader .....	3-14
Table 3-8 Waste Composition of Front Loader .....	3-16
Table 3-9 Waste Composition of Side Loader.....	3-17
Table B-1 First Season Waste Composition .....	B-2
Table B-2 First Season Waste Composition .....	B-4
Table B-3 First Season Waste Composition .....	B-6
Table B-4 First Season Waste Composition .....	B-8

## List of Appendices

---

Appendix A Description of Waste Categories

Appendix B Waste Composition of Sample Loads for Season 1

Appendix C Waste Composition of Sample Loads for Season 2

Appendix D Driver Questionnaire and Field Data Sheet

Appendix E Permit Approval Class II Recycling Permit

Appendix F Calculation for Number of Samples



# Executive Summary

The Massachusetts Department of Environmental Protection (MassDEP) regulations at 310 CMR 19.300 et seq. (Class II Recycling Program) establishes requirements in order for a Waste-to-Energy (WTE) Facility to qualify to be eligible to sell renewable energy credits (RECs), under the Department of Energy Resources Renewable Energy Portfolio Standards at 225 CMR 15.00. Among the requirements within the Class II Recycling Program is to conduct a Waste Characterization Study (WCS) for each respective Facility during the calendar year 2010 and to repeat the WCS every three years. The WCS is to be conducted in accordance with the MassDEP 2013 Waste Characterization Scope and Methodology Guidance (MassDEP WCS Guidance), and the WCS Protocol prepared by Brown and Caldwell (BC), subsequently approved by MassDEP on October 23, 2012.

As stated in the MassDEP WCS Guidance, the goals of the WCS include the following:

1. Characterize the solid waste disposal stream at the Facility;
2. Provide statewide characterization information;
3. Allow MassDEP to utilize the information to measure the success of waste reduction efforts;
4. Identify specific materials for increased diversion; and
5. Help guide MassDEP policy and program initiatives in solid waste management.


BC was retained by Wheelabrator North Andover, Inc. in 2010 and 2013 to develop and implement the WCS at the North Andover WTE Facility in North Andover, MA (the Facility). The WCS employs manual sorting of representative samples of incoming waste representing the various sectors of the solid waste stream received at the Facility.

The WCS was designed in accordance with the methodologies described in ASTM D5321-92(2008), Test Method for Determination of the Composition of Unprocessed Municipal Solid Waste, as required in Section I (Scope), of the MassDEP WCS Guidance. The number of samples needed to achieve a 90% confidence level with a 10% precision was found to be 52. The samples were evenly distributed over the spring and summer seasons in calendar year 2013, as required by MassDEP (26 minimum samples per season). The sample allocation for the WCS was based on the cardboard waste component, and selected proportionately between Residential and Industrial/Commercial/ Institutional (ICI) wastes using Facility scale house data, which resulted in a distribution of 71% Residential and 29% ICI. The first season of the 2013 WCS was conducted between April 29 and May 3, 2013, and the second season was conducted between July 15 and July 19, 2013.

Figure ES-1 provides a general overview of the waste composition at the Facility during the study periods. There are thirteen major waste categories and 62 sub-categories defined in MassDEP WCS Guidance. During the study period, the primary components of the waste at the Facility were organic material at 28.4%, paper at 22.9%, plastics at 12.1%, and construction and demolition materials at 18.0% of the waste stream. Further detail into the breakdown of waste composition for the Facility is provided in Section 3 of this report.



**Figure ES-1**  
**2013 Overall Waste Composition**  
**Wheelabrator North Andover, Inc.**



In addition, Table ES-1 is provided to supplement Figure ES-1, and presents a comparative summary of the results of the 2010 and 2013 WCS at the Facility. The categorization is based on the thirteen major waste categories provided in the MassDEP WCS Guidance, as well as separating the waste into Residential and ICI sectors. Separation of the data into Residential and ICI sectors is based on Facility scalehouse data on the type of haul vehicle for a two week period. This allocation into Residential and ICI sectors excluded transfer trailers, which were not included in the WCS.

**Table ES-1**  
**Summary of Waste Composition**  
**Wheelabrator North Andover, Inc.**  
**2010 and 2013**

	2010			2013*		
WASTE CATEGORIES	Residential	ICI	Overall Waste Composition 77% Res:23% ICI	Residential	ICI	Overall Waste Composition 71% Res:29% ICI
PAPER	29.7%	30.8%	29.9%	20.1%	29.6%	22.9%
PLASTICS	12.6%	14.2%	13.0%	11.2%	14.3%	12.1%
METALS	4.0%	3.8%	3.9%	3.5%	4.3%	3.7%
GLASS	3.1%	3.3%	3.1%	1.7%	1.7%	1.7%
ORGANIC MATERIAL	20.7%	16.2%	19.7%	32.3%	18.7%	28.4%
CONSTRUCTION AND DEMOLITION	13.6%	17.5%	14.5%	17.2%	19.7%	18.0%
HOUSEHOLD HAZARDOUS WASTE	6.2%	4.6%	5.9%	2.1%	2.8%	2.3%
ELECTRONICS	1.6%	2.3%	1.8%	1.4%	1.6%	1.4%
TIRES & OTHER RUBBER	0.1%	0.0%	0.1%	0.0%	0.0%	0.0%
TEXTILES	2.4%	3.0%	2.6%	1.3%	0.3%	1.0%
BULKY MATERIALS	4.8%	2.4%	4.2%	6.9%	3.1%	5.8%
RESTAURANT FATS, OILS & GREASE	0.5%	1.3%	0.7%	0.5%	0.2%	0.5%
OTHER MISCELLANEOUS	0.9%	0.6%	0.8%	1.1%	3.2%	1.7%
TOTAL	100%	100%	100%	100%	100%	100%

\*Percent waste component reductions from 2010 WCS to 2013 WCS are highlighted in red

## Section 1

# Introduction

## 1.1 Background

The Green Communities Act (Chapter 169 of the Acts of 2008) identifies a Waste-to-Energy (WTE) facility in commercial operation prior to December 31, 1997, using conventional municipal solid waste technology to generate electricity, as a Class II renewable energy generating source if it “operates or contracts for one or more recycling programs approved by the department of environmental protection.” Massachusetts Department of Environmental Protection (MassDEP) regulations at 310 CMR 19.300 et seq. (Class II Recycling Program) establishes further requirements in order to qualify to be eligible to sell renewable energy credits (RECs) under the Department of Energy Resources Renewable Energy Portfolio Standards at 225 CMR 15.00. Among these requirements is to conduct a Waste Characterization Study (WCS) during the calendar year 2010, and every three years thereafter.

The objective of the WCS is to attempt to characterize the solid waste stream brought to a WTE facility for disposal. The WCS was conducted in accordance with the following documents and permit approvals.

- Permit Modification Approval – Final Decision, Class II Recycling Program, Transmittal No. X228987, dated September 25, 2009
- MassDEP 2013 Class II Recycling Program, Waste Characterization Scope and Methodology Guidance (MassDEP WCS Guidance)
- Wheelabrator North Andover, Inc., Waste Characterization Study Protocol, prepared by Brown and Caldwell, revised October 31, 2012
- 2013 Waste Characterization Study Protocol Approval, dated October 23, 2012

The MassDEP WCS Guidance establishes a protocol for the WCS that implements ASTM D 5231–92(2008) Standard Test Method for Determination of the Composition of Unprocessed Municipal Solid Waste.

## 1.2 Introduction

The Wheelabrator North Andover Inc. facility (the Facility) is located at 285 Holt Road, North Andover, MA, and began operating in 1985. The Facility is designed to combust 1,500 tons per day of municipal solid waste (MSW), and consists of two mass-burn, municipal waste combustion units. The Facility currently serves 24 communities via contract, as presented in Table 1-1. Non-contract or "spot market" customers vary daily and comprise the remainder of the solid waste disposal capacity at the Facility. A site locus map is included as Figure 1-1, and an aerial map is included as Figure 1-2.

The WCS protocol for the North Andover Facility 2013 WCS required the data collection to be conducted for the spring season between April 15 and June 15, and for the fall season between July 15 and September 15. The field work was conducted by Brown and Caldwell (BC) during April 29 – May 3, 2013, and July 15 – 19, 2013. The WCS was performed in accordance with the Class II Recycling Program, MassDEP’s WCS Guidance, the Facility Class II Recycling Permit issued by MassDEP on September 25, 2009, and the WCS Protocol prepared by Brown and Caldwell (BC) and approved by MassDEP on October 23, 2012.

<b>Table 1-1 Wheelabrator North Andover, Inc. Service Area</b>			
Amesbury	Hamilton	Manchester	Wenham
Andover	Hiltz Disposal (Groveland)	Methuen	West Newbury
Arlington		Newburyport	Wilmington
Belmont	Ipswich	North Andover	Winchester
Billerica	Lexington	Peabody	
Boxborough	Lincoln	Pepperell	
Carlisle	Lowell	Watertown	

The results of the North Andover 2013 WCS are presented in this report. These results include the following:

1. Final WCS Design: An account of the variation in the sampling period, number and categorical allocation of waste samples, vehicles sampled, loads sampled, and final sort design.
  - Waste composition for each sample load for the spring season is presented in Appendix B and for the summer season is presented in Appendix C.
2. Overall Composition of Waste: A summary account of the overall waste composition of the waste stream.
  - Table ES-1 and Figure ES-1 provide a summary of the overall composition of the waste stream measured by the WCS for the Facility.
3. Composition by Sectors:
  - A summary account of the composition of the waste stream, grouped into Residential and ICI sectors, is presented in Section 3.4 of this report.
4. Composition by Vehicle Haul Type: A summary account of the composition of the waste stream grouped by the following vehicle haul types:
  - Roll-off - open top
  - Roll-off - closed top
  - Roll-off – compactor
  - Rear loading packer
  - Front loading packer
  - Side loading packer

The results of the composition by vehicle haul type are presented in Section 3.5 of this report.

During the development of the WCS protocol and discussions with MassDEP regarding the WCS, it was decided that transfer trailers would not be sampled and not included in the WCS. Therefore, this report excludes any data related to transfer trailers, as they were not sampled nor included in the WCS.

## Section 2

# Methodology

The methodology used for the WCS was based on the MassDEP WCS Guidance established in September 2009, which references the methodology and protocol described in ASTM D5321-92(2008), Test Method for Determination of the Composition of Unprocessed Municipal Solid Waste. As previously described, sampling and data collection was implemented over the course of two sampling periods in 2013, to account for seasonal variation.

### 2.1 Allocation of Number of Samples by Haul Type

Statistical experimental design is effective in eliminating known sources of bias, guarding against unknown sources of bias, ensuring that the study provides precise information on the subject of interest, and providing an economical design through minimization of wasted effort. All of the MassDEP WCS Guidelines were considered during the design of the WCS field work and data interpretation, to ensure quality in the study plan. The number of samples sorted was determined based on statistical criteria specified by MassDEP and calculated according to the ASTM D-532-92(2008) method. The number of samples was determined as a function of the waste components to be sorted, and the desired precision as applied to each component. The calculation is presented in Appendix F. The MassDEP WCS Guidelines require a 90% confidence level and 10% precision.

Corrugated cardboard required the highest number of samples to meet 90% confidence level and 10% precision. Therefore, to satisfy these requirements, a minimum of 52 samples must be selected and sorted at the Facility over both seasonal events. The total required number was divided equally between both seasons, with 26 samples being conducted during the spring season event and 26 during the fall season event.

The MassDEP WCS Guidance defines Residential, ICI, and Unacceptable waste as follows:

- Residential – vehicles in which 80% or more of the waste is from residential sources (single family or multi-family). Typically these vehicles will include residential drop-off containers (usually roll-offs) and rear-load packer trucks.
- ICI – vehicles in which 80% or more of the waste is from ICI sources. Typically these vehicles will include compactor boxes, open top boxes and front-load packers.
- Unacceptable Loads – loads that contain less than 80% of either Residential or ICI waste, loads that are more than 50% construction and demolition material, and loads originating from out of state.

Site specific data was also used in developing the sampling plan for the Facility. This was accomplished by determining the number of samples proportional to the numbers of different vehicles hauling waste (vehicle haul type) of the incoming waste at the Facility, based on Facility scalehouse data during a one-year period.

Data from all three Wheelabrator facilities in Massachusetts indicates that the distribution of incoming waste types does not closely resemble the statewide data provided by MassDEP of 46% Residential and 54% ICI. Each individual Facility's distribution varied and this is accounted for in the WCS. Table 2.1 presents the number of planned and actual samples by vehicle haul type for the Facility.

<b>Table 2-1</b> <b>Number and Allocation of Samples - Wheelabrator North Andover, Inc.</b>			
<b>Haul Type</b>	<b>Tonnage Distribution, %</b>	<b>Planned Number of Samples based on Facility Tonnage Distribution</b>	<b>Actual Number of Samples</b>
Roll-off - open top	1.0%	1	2
Roll-off - closed top	4.0%	2	3
Roll-off - compactor	4.0%	2	4
Rear loading packer	70.0%	36	34
Side loading packer	1.0%	1	1
Front loading packer	21.0%	11	11
<b>Total</b>	<b>100 %</b>	<b>53</b>	<b>55</b>

Notes: 1. The number of samples were determined proportional to the waste tonnage delivered by haul type. The distribution of waste tonnage for the Facility of 42% Residential and 58% ICI closely resembled the statewide data provided by MassDEP of 46% Residential and 54% ICI.

## 2.2 Sampling Procedure

In general terms, the sampling procedure consisted of load selection, the physical sorting of the sample, and the documentation of the data for each sample. These WCS components are discussed in the following sections, and as a whole constitute the sampling procedures for the collection of the data.

The waste categories used in the WCS were as specified in the MassDEP WCS Guidance, and consisted of 13 categories and 62 sub-categories. These categories and sub-categories are described in detail in Appendix A. A sampling period of five (5) days was used for each season, with the number of vehicles sampled per day proportional to the distribution of vehicle types incoming to the Facility during a one year period. In applying the tonnage distribution percentages to the required number of vehicles, it was determined that a minimum of 52 vehicles should be sampled for the WCS; 27 vehicles were sampled during the spring season sampling event and 28 vehicles were sampled during the summer season sampling event.

### 2.2.1 Load Selection

The types of haul vehicles sampled were based on the distribution of tonnage by vehicle type at the Facility. Individual vehicles for sampling were selected at random during each day of the sampling period, to provide a representative cross-section of the incoming waste stream. The selection of vehicles was conducted in accordance with ASTM test method D5231-92(2008), as required in the MassDEP WCS Guidance.

Once a vehicle was identified to be sampled, the driver was interviewed and the information provided was recorded on a Driver Questionnaire form. A copy of the Driver Questionnaire form is provided in Appendix D. The following information was recorded on the Driver Questionnaire form:

- Time and Date
- Facility Truck Identification Number
- Hauling company and Truck type
- Truck weight from scale ticket
- Waste type based on driver's route
- Other route information, including precipitation

Following the selection of the vehicle to be sampled and completion of the Driver Questionnaire form, the vehicle was directed to a specific location on the tipping floor where the entire load was deposited. All handling and manipulation of the discharged load was conducted on a clean surface of the tipping floor. Figure 1-3 is provided to show the general location of the sorting area used at the Facility during the WCS.

### 2.2.2 Sorting Procedures

Unprocessed solid waste is a heterogeneous mixture of materials. Therefore, care was taken during the sorting process in order to obtain representative samples. Once the vehicle deposited its waste load on a segregated area of the tipping floor, the Facility-operated front-end loader was used to cut the waste load longitudinally in order to obtain a representative cross-section of the waste material. The mass of material was gauged visually to determine if it satisfied the desired weight of the sample (approximately 1,000 pounds). The waste was then mixed with the front-end loader and quartered into four equal piles. As required in ASTM D5231-92(2008), using a random method of selection to minimize or eliminate bias, one quarter of minimum 225 pounds was selected as the sorting sample. The sorting sample was then transferred to the designated coned-off protected sorting area for sorting into appropriate waste categories and sub-categories. Material of each sub-category was placed into one of 62 20-gallon plastic bins to be weighed and recorded.

After the waste was sorted, weighed, and the amounts recorded, materials that were able to be recycled were placed in the appropriate bin or roll-off container for recycling. Some of the material that was recycled included the following:

- Glass
- Metal
- Single polymer plastics
- Cardboard
- Recyclable Paper

If a large oversized item was discovered in the selected sample load, (e.g. furniture, large white good, etc.), a visual estimation of its weight and the full vehicle load weight were noted. The estimated weight of the item as a percentage of the load was calculated. If an oversize item composed a large weight percentage of the sorting sample, a notation was added on the field sheet, and the item was weighed and information documented on the field sheet.

### 2.2.3 Documentation of Sample Data

After sorting was completed, the sorted waste samples were weighed and the results recorded for each of the 62 sub-categories. Tare weights for the bins were determined between each sorting day. At the conclusion of the sorting week at the Facility, the data from the field sheets was entered into spreadsheets for analysis.

Documentation of each load sampled and the percentage of waste composed in each sample from the spring sampling season is provided in Appendix B. Documentation of each load sampled and the percentage of waste composed in each sample from the summer sampling season is provided in Appendix C.

## Section 3

# Results

### 3.1 Method of Data Analysis

The lower and upper confidence intervals indicate the likelihood that the population (the actual composition of the entire waste stream) falls close to the sample mean (the samples analyzed in the study). The lower and upper bound throughout this report have been calculated at 90 percent level of confidence. This means we can be 90 percent confident that the true fraction of this material in the overall population falls between the lower and upper bound shown. The inverse is also true; there is a 10 percent chance that the true mean falls outside the intervals. For example, if the mean composition of cardboard in front end loaders was 11.2 percent, we can be 90 percent confident that the actual fraction of cardboard in the waste stream falls between 9.3 percent and 13.1 percent.

The results of the 2013 WCS for both seasons at the Facility are included in this section. The data obtained during each of the sampling seasons was taken from the field data sheets and input into spreadsheets. Analysis of the data consisted of calculating the mean waste composition, standard deviation, and confidence intervals using the composition of each sorted sample.

### 3.2 Overall Composition of Waste

This section describes the overall composition of waste calculated during the WCS for the Facility. Figure 3-1 is a bar graph depicting the 62 sub-categories in the waste sampled, during the study periods. As can be seen in Figure ES-1, four categories constitute approximately 81% of the waste stream incoming to the Facility during the WCS. Organic material constitutes the highest percentage of material at 28%, followed by paper at approximately 23%. C&D materials represented approximately 18% and plastics represented about 12% of the materials during the WCS. The percentage of organic material is substantially more than determined during the 2010 WCS. This increase in organic waste is primarily attributed to an increase in food waste and remainder composite organics observed during each sampling season.



Figure 3-1 OVERALL COMPOSITION OF WASTE - WHEELABRATOR NORTH ANDOVER, INC.




Table 3-1 below presents the data for all 62 waste sub-categories as described in MassDEP's WCS Guidance. The information is based on the data gathered from 55 samples during the 2013 WCS at the Facility.

Table 3-1 Overall Waste Composition at Wheelabrator North Andover, Inc.				
Categories		Residential 100%	ICI 100%	Overall WCS 71%(R):29%(ICI)
1.0	<b>PAPER</b>			22.9%
1.1	Uncoated Corrugated Cardboard/Kraft Paper	4.6%	10.8%	6.4%
1.2	Waxed Cardboard	0.0%	1.1%	0.3%
1.3	High Grade Office Paper	0.5%	1.5%	0.8%
1.4	Magazines/Catalogs	1.1%	1.2%	1.1%
1.5	Newsprint	1.4%	2.7%	1.8%
1.6	Other Recyclable Paper	3.9%	3.6%	3.8%
1.7	Compostable Paper	7.5%	5.9%	7.1%
1.8	Remainder/Composite Paper	1.0%	2.8%	1.5%
2.0	<b>PLASTICS</b>			12.1%
2.1	PET Beverage Containers	0.5%	0.5%	0.5%
2.2	PET Containers other than Beverage Containers	0.2%	0.2%	0.2%
2.3	Plastic MA Deposit Beverage Containers	0.3%	0.3%	0.3%
2.4	HDPE Bottles, colored and natural	0.5%	0.4%	0.5%
2.5	Plastic Tubs and lids	0.1%	0.1%	0.1%
2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	1.2%	0.9%	1.1%
2.7	Expanded Polystyrene Food Grade	0.5%	0.4%	0.5%
2.8	Expanded Polystyrene Non-food Grade	0.0%	1.3%	0.4%
2.9	Bulk Rigid Plastic Items	2.1%	3.6%	2.5%
2.10	Film (non-bag commercial industrial packaging film)	1.0%	1.4%	1.1%
2.11	Grocery and other Merchandise Bags	0.5%	0.3%	0.4%
2.12	Other Film means plastic film	3.2%	3.2%	3.2%
2.13	Remainder/Composite Plastic	1.2%	1.8%	1.3%
3.0	<b>METALS</b>			3.7%
3.1	Aluminum Beverage Containers (non-MA deposit)	0.1%	0.1%	0.1%
3.2	Aluminum MA Deposit Beverage Containers	0.1%	0.1%	0.1%
3.3	Tin/Steel Containers	0.5%	0.6%	0.5%
3.4	Other Aluminum	0.3%	0.3%	0.3%
3.5	Other Ferrous and non-ferrous	0.4%	1.2%	0.6%
3.6	White Goods	0.0%	0.0%	0.0%
3.7	Remainder Composite Metal	2.1%	2.0%	2.1%
4.0	<b>GLASS</b>			2.2%
4.1	Glass Beverage Containers (non-MA deposit)	1.3%	0.5%	1.1%
4.2	Other Glass Packaging Containers (non-MA deposit)	0.4%	0.5%	0.4%
4.3	Glass MA Deposit Beverage Containers	0.2%	0.5%	0.3%
4.4	Remainder/Composite Metal	0.3%	0.7%	0.5%
5.0	<b>ORGANIC MATERIAL</b>			18.0%
5.1	Food Waste	17.9%	12.5%	16.3%
5.2	Branches and Stumps	0.9%	0.3%	0.7%
5.3	Prunings, Trimmings, Leaves and Grass	9.9%	3.1%	7.9%
5.4	Manures	0.2%	0.1%	0.2%
5.5	Remainder/Composite Organic	3.5%	2.7%	3.3%

<b>Table 3-1 Overall Waste Composition at Wheelabrator North Andover, Inc. Continued</b>				
<b>Categories</b>		<b>Residential 100%</b>	<b>ICI 100%</b>	<b>Overall WCS 71%(R):29% (ICI)</b>
6.0	<b>CONSTRUCTION AND DEMOLITION</b>			18.0%
6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%	0.0%
6.2	Aggregates, Stone, Rock	0.7%	0.0%	0.5%
6.3	Wood – Treated	4.9%	5.6%	5.1%
6.4	Wood – untreated	3.7%	5.1%	4.1%
6.5	Asphalt Roofing	0.0%	4.3%	1.3%
6.6	Drywall/ Gypsum Board	0.8%	0.0%	0.5%
6.7	Carpet and Carpet Padding	5.0%	3.5%	4.6%
6.8	Remainder/Composite Construction and Demolition	2.3%	1.2%	2.0%
7.0	<b>HOUSEHOLD HAZARDOUS WASTE</b>			2.3%
7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%	0.0%
7.2	Batteries – Lead Acid	0.0%	0.3%	0.1%
7.3	Batteries – Other	0.1%	0.0%	0.1%
7.4	Paint	0.0%	0.7%	0.2%
7.5	Bio-Hazardous (Diapers)	1.9%	1.7%	1.9%
7.6	Vehicle and Equipment Fluids	0.0%	0.0%	0.0%
7.7	Empty Metal, Glass, and Plastic Containers (contained toxic materials)	0.0%	0.0%	0.0%
7.8	Pesticides and Fertilizers	0.0%	0.0%	0.0%
7.9	Other Hazardous or Household Hazardous Waste	0.1%	0.0%	0.0%
8.0	<b>ELECTRONICS</b>			1.4%
8.1	Computer-related Electronics	0.1%	0.0%	0.1%
8.2	Other “brown goods”	0.5%	0.4%	0.5%
8.3	Televisions and Computer Monitors	0.7%	1.1%	0.8%
9.0	<b>OTHER MATERIALS</b>			7.3%
9.1	Tires and other rubber	1.3%	0.3%	1.0%
9.2	Textiles	6.9%	3.1%	5.8%
9.3	Bulky materials	0.5%	0.2%	0.5%
9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%	0.0%
10.0	<b>OTHER MISCELLANEOUS</b>	1.1%	3.2%	1.7%

### 3.3 Composition of Waste by Sampling Season

A comparison of the waste composition by sampling season is presented in Table 3-2. It was determined that a minimum of 52 vehicles should be sampled for the WCS; 27 vehicles were sampled during the spring season sampling event and 28 vehicles were sampled during the summer season sampling event.

Table 3-2 Composition of Waste by Season					
Categories		Season 1		Season 2	
		Average	At 90 % confidence Level (+/-)	Average	At 90 % confidence Level (+/-)
1.0	<b>PAPER</b>				
1.1	Uncoated Corrugated Cardboard/Kraft Paper	4.6%	1.8%	9.35%	3.0%
1.2	Waxed Cardboard	0.1%	0.1%	0.85%	1.0%
1.3	High Grade Office Paper	1.7%	1.3%	0.61%	0.3%
1.4	Magazines/Catalogs	1.3%	0.4%	1.00%	0.5%
1.5	Newsprint	1.7%	0.9%	2.25%	1.5%
1.6	Other Recyclable Paper	4.4%	1.6%	3.90%	1.8%
1.7	Compostable Paper	8.2%	1.5%	5.63%	1.0%
1.8	Remainder/Composite Paper	1.9%	1.4%	1.87%	1.1%
2.0	<b>PLASTICS</b>				
2.1	PET Beverage Containers	0.6%	0.1%	0.26%	0.1%
2.2	PET Containers other than Beverage containers	0.2%	0.1%	0.16%	0.1%
2.3	Plastic MA Deposit Beverage Containers	0.1%	0.1%	0.46%	0.1%
2.4	HDPE Bottles, colored and natural	0.5%	0.1%	0.39%	0.2%
2.5	Plastic Tubs and lids	0.2%	0.1%	0.07%	0.1%
2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	1.1%	0.2%	1.00%	0.2%
2.7	Expanded Polystyrene Food Grade	0.6%	0.3%	0.35%	0.1%
2.8	Expanded Polystyrene Non-food Grade	1.0%	1.5%	0.54%	0.9%
2.9	Bulk Rigid Plastic Items	2.7%	1.5%	3.48%	2.0%
2.10	Film (non-bag commercial and industrial packaging film)	0.5%	0.5%	1.77%	0.5%
2.11	Grocery and other Merchandise Bags	0.5%	0.1%	0.29%	0.1%
2.12	Other Film means plastic film	4.5%	0.7%	2.18%	0.8%
2.13	Remainder/Composite Plastic	1.8%	1.2%	1.73%	0.8%
3.0	<b>METALS</b>				
3.1	Aluminum Beverage Containers (non-MA deposit)	0.2%	0.1%	0.06%	0.0%
3.2	Aluminum MA Deposit Beverage Containers	0.0%	0.0%	0.18%	0.1%
3.3	Tin/Steel Containers	1.1%	0.5%	0.38%	0.1%
3.4	Other Aluminum	0.2%	0.1%	0.37%	0.2%
3.5	Other Ferrous and non-ferrous	1.3%	1.3%	0.45%	0.3%
3.6	White Goods	0.0%	0.0%	0.00%	0.0%
3.7	Remainder Composite Metal	2.2%	1.4%	1.41%	1.2%
4.0	<b>GLASS</b>				
4.1	Glass Beverage Containers (non-MA deposit)	1.4%	0.6%	0.78%	0.4%
4.2	Other Glass Packaging Containers (non-MA deposit)	0.4%	0.2%	0.39%	0.2%
4.3	Glass MA Deposit Beverage Containers	0.1%	0.1%	0.54%	0.3%
4.4	Remainder/Composite Metal	1.1%	0.8%	0.30%	0.2%

Table 3-2 Composition of Waste by Season Continued

Categories		Season 1		Season 2	
		Average	At 90 % confidence Level (+/-)	Average	At 90 % confidence Level (+/-)
5.0	<b>ORGANIC MATERIAL</b>				
5.1	Food Waste	13.9%	2.8%	17.99%	4.4%
5.2	Branches and Stumps	0.4%	0.7%	0.88%	0.7%
5.3	Prunings, Trimmings, Leaves and Grass	6.1%	2.9%	6.16%	3.0%
5.4	Manures	0.2%	0.3%	0.21%	0.2%
5.5	Remainder/Composite Organic	4.6%	1.0%	1.72%	0.7%
6.0	<b>CONSTRUCTION AND DEMOLITION</b>				
6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.1%	0.00%	0.0%
6.2	Aggregates, Stone, Rock	0.2%	0.2%	0.66%	1.0%
6.3	Wood - Treated	3.9%	1.9%	6.74%	3.5%
6.4	Wood - untreated	5.6%	3.6%	2.10%	1.3%
6.5	Asphalt Roofing	0.0%	0.0%	2.67%	3.1%
6.6	Drywall/Gypsum Board	1.6%	1.6%	0.09%	0.1%
6.7	Carpet and Carpet Padding	3.2%	1.9%	4.15%	2.6%
6.8	Remainder/Composite Construction and Demolition	1.5%	1.0%	1.82%	1.2%
7.0	<b>HOUSEHOLD HAZARDOUS WASTE</b>				
7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%	0.00%	0.0%
7.2	Batteries - Lead Acid	0.1%	0.3%	0.01%	0.0%
7.3	Batteries - Other	0.1%	0.0%	0.01%	0.0%
7.4	Paint	0.9%	0.9%	0.00%	0.0%
7.5	Bio-Hazardous (Diapers)	2.1%	0.7%	1.54%	0.6%
7.6	Vehicle and Equipment Fluids	0.0%	0.0%	0.00%	0.0%
7.7	Empty Metal, Glass, and Plastic Containers (contained toxic materials)	0.1%	0.1%	0.01%	0.0%
7.8	Pesticides and Fertilizers	0.0%	0.0%	0.00%	0.0%
7.9	Other Hazardous or Household Hazardous Waste	0.0%	0.0%	0.08%	0.1%
8.0	<b>ELECTRONICS</b>				
8.1	Computer-related Electronics	0.0%	0.0%	0.18%	0.2%
8.2	Other "brown goods"	0.2%	0.2%	0.55%	0.5%
8.3	Televisions and Computer Monitors	0.2%	0.3%	1.59%	1.2%
9.0	<b>OTHER MATERIALS</b>				
9.1	Tires and other rubber	1.1%	1.0%	0.96%	0.7%
9.2	Textiles	4.3%	1.8%	5.09%	1.7%
9.3	Bulky materials	1.4%	1.2%	0.00%	0.0%
9.4	Restaurant Fats, Oils and Grease	0.2%	0.4%	0.00%	0.0%
10.0	<b>OTHER MISCELLANEOUS</b>	1.7%	2.0%	1.75%	0.6%

### 3.4 Composition of Waste by Sector


This section provides a summary account of the overall composition of the waste stream encountered during the WCS grouped into the two sectors of Residential and ICI waste. The residential waste composition presented below is based on the assumption that all rear loading packers and side loaders are classified as residential waste. The results indicate that the Residential sector makes up approximately 71% of the waste stream and the ICI sector makes up approximately 29% of the waste stream.

Figures 3-2 and 3-3 provide breakdown of the waste stream into the 13 major categories defined by MassDEP.

### 3.4.1 Residential Sector

Figure 3-2 displays the distribution of the Residential waste sector at the Facility over the 13 main categories of waste described in the MassDEP WCS Guidance, based on the 55 samples analyzed over the course of both sampling seasons. Organic material comprised the most material in the residential waste stream at 32.3% (21% in 2010), and paper constituted next highest percentage at 20.1 % (29.7% in 2010). C&D were the third highest at 17.2% of materials (13.6% in 2010), plastic was fourth highest at 11.2% (12.6% in 2010), and bulky material were the fifth highest at 6.9%.


**Figure 3-2**  
**Residential Waste Composition**  
**Wheelabrator North Andover, Inc.**



### 3.4.2 ICI Sector

Figure 3-3 displays the distribution of the ICI waste sector at the Facility over the 13 main categories of waste described in the MassDEP WCS Guidance, based on the 55 samples analyzed over the course of both sampling seasons. Paper comprised the most material in the ICI waste stream at 29.6% (30.8% in 2010), with C&D constituting the second highest percentage at approximately 19.7% (17.5% in 2010). Organic materials represented approximately 18.7% (16.2% in 2010) and plastic material represented around 14.3% (14.2% in 2010) of the materials found in the ICI waste stream.

**Figure 3-3**  
**ICI Waste Composition**  
**Wheelabrator North Andover, Inc.**



### 3.4.3 Unacceptable Loads

Unacceptable loads are defined as loads that contain less than 80% of either Residential or ICI waste, loads that are more than 50% construction and demolition material, and loads originating from out of state. During the WCS, no out of state loads were identified based on interviews with the drivers of vehicles selected for sampling.

The driver interview process allowed the WCS crew supervisor to identify any loads that may have contained less than 80% waste of either Residential or ICI sectors, and thereby be determined to be unacceptable. There were no loads identified during the WCS that were determined to be unacceptable for the WCS.

### 3.5 Waste Composition by Haul Type

Tables 3-4 through 3-8 describe the waste composition by vehicle haul type, based on the 164 samples sorted during the WCS time period in 2013, for all three Wheelabrator facilities in Massachusetts.

Including all vehicles sampled during the WCS for the three facilities allows for a more accurate calculation of the results instead of limiting the data to one facility. For example, the side loader type would be limited to one vehicle if only the North Andover data were included.

The summary account of the waste composition by haul type has been categorized by the six vehicles listed in Table 3-3. Table 3-3 also indicates how many vehicles of each type were sampled during the WCS.

<b>Table 3-3</b> <b>Number and Allocation of Samples by</b> <b>Vehicle Type</b> <b>Wheelabrator North Andover, Inc.</b>	
<b>Haul Type</b>	<b>Number of Vehicles Sampled</b>
Roll-off - open top	2
Roll-off - closed top	3
Roll-off - compactor	4
Rear loading packer	34
Side loading packer	1
Front loading packer	11
<b>Total</b>	<b>55</b>



Table 3-4 Waste Composition of Roll-off Open Top				
WASTE CATEGORIES			Average	90% Confidence Level (+/-)
1.0 PAPER	1.1	Uncoated Corrugated Cardboard/Kraft Paper	12.1%	7.9%
	1.2	Waxed Cardboard	0.0%	0.0%
	1.3	High Grade Office Paper	0.3%	0.3%
	1.4	Magazines/Catalogs	0.5%	0.5%
	1.5	Newsprint	1.2%	1.2%
	1.6	Other Recyclable Paper	3.4%	2.3%
	1.7	Compostable Paper	6.0%	3.3%
	1.8	Remainder/Composite Paper	0.7%	1.1%
2.0 PLASTICS	2.1	PET Beverage Containers	0.4%	0.3%
	2.2	PET Containers other than Beverage Containers	0.1%	0.1%
	2.3	Plastic MA Deposit Beverage Containers	0.1%	0.1%
	2.4	HDPE Bottles, colored and natural	0.3%	0.4%
	2.5	Plastic Tubs and lids	0.2%	0.3%
	2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.3%	0.2%
	2.7	Expanded Polystyrene Food Grade	0.7%	1.0%
	2.8	Expanded Polystyrene Non-food Grade	3.1%	5.8%
	2.9	Bulk Rigid Plastic Items	3.4%	5.1%
	2.1	Film (non-bag commercial and industrial packaging film)	1.1%	1.2%
	2.11	Grocery and other Merchandise Bags	0.2%	0.2%
	2.12	Other Film means plastic film	2.5%	1.1%
	2.13	Remainder/Composite Plastic	1.4%	1.0%
3.0 METALS	3.1	Aluminum Bev. Containers (non-MA deposit containers)	0.1%	0.1%
	3.2	Aluminum MA Deposit Beverage Containers	0.1%	0.1%
	3.3	Tin/Steel Containers	0.0%	0.1%
	3.4	Other Aluminum	0.1%	0.1%
	3.5	Other Ferrous and non-ferrous	1.9%	2.3%
	3.6	White Goods	0.0%	0.0%
	3.7	Remainder/Composite Metal	1.3%	1.2%
4.0 GLASS	4.1	Glass Bev. Containers (non-MA deposit containers)	0.2%	0.2%
	4.2	Other Glass Packaging Cont. (non-MA deposit)	0.3%	0.5%
	4.3	Glass MA Deposit Beverage Containers	0.0%	0.0%
	4.4	Remainder/Composite Glass	0.2%	0.2%
5.0 ORGANIC	5.1	Food Waste	4.2%	3.1%
	5.2	Branches and Stumps	0.0%	0.0%
	5.3	Prunings, Trimmings, Leaves and Grass	2.4%	3.2%
	5.4	Manures	0.0%	0.0%
	5.5	Remainder/Composite Organic	1.5%	1.6%

**Table 3-4 Waste Composition of Roll-off Open Top Continued**

WASTE CATEGORIES			Average	90% Confidence Level (+/-)
<b>6.0 C &amp; D</b>	6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%
	6.2	Aggregates, Stone, Rock	0.0%	0.1%
	6.3	Wood – Treated	12.2%	11.0%
	6.4	Wood – untreated	11.1%	11.4%
	6.5	Asphalt Roofing	0.0%	0.0%
	6.6	Drywall/Gypsum Board (Identify if Chinese Drywall)	1.4%	2.6%
	6.7	Carpet and Carpet Padding	6.9%	7.3%
	6.8	Remainder/Composite Construction and Demolition	2.6%	3.1%
<b>7.0 HHW</b>	7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%
	7.2	Batteries – Lead Acid	0.0%	0.0%
	7.3	Batteries – Other	0.1%	0.1%
	7.4	Paint	0.0%	0.0%
	7.5	Bio-Hazardous	0.1%	0.2%
	7.6	Vehicle and Equipment Fluids	0.0%	0.0%
	7.7	Metal, Glass, and Plastic Cont.(cont. toxic materials)	0.0%	0.0%
	7.8	Pesticides and Fertilizers	0.0%	0.1%
<b>8.0 E&amp;EIT</b>	7.9	Other Hazardous or Household Hazardous Waste	0.0%	0.0%
	8.1	Computer-related Electronics	0.1%	0.1%
	8.2	Other “brown goods”	0.3%	0.4%
<b>9.0 OTHER</b>	8.3	Televisions and Computer Monitors	4.1%	4.3%
	9.1	Tires and other rubber	5.4%	8.2%
	9.2	Textiles	4.2%	6.6%
	9.3	Bulky materials	0.2%	0.4%
<b>10</b>	9.4	Restaurant Fats, Oils and Grease	0.0%	0.1%
	10	<b>OTHER MISCELLANEOUS</b>	0.8%	0.9%

**Table 3-5 Waste Composition of Roll-off Closed Top**

WASTE CATEGORIES			Average	90% Confidence Level (+/-)
<b>1.0 PAPER</b>	1.1	Uncoated Corrugated Cardboard/Kraft Paper	10.3%	11.4%
	1.2	Waxed Cardboard	0.0%	0.0%
	1.3	High Grade Office Paper	4.3%	6.5%
	1.4	Magazines/Catalogs	1.2%	1.6%
	1.5	Newsprint	1.6%	2.5%
	1.6	Other Recyclable Paper	6.8%	8.3%
	1.7	Compostable Paper	7.1%	5.1%
	1.8	Remainder/Composite Paper	6.4%	7.8%
<b>2.0 PLASTICS</b>	2.1	PET Beverage Containers	0.4%	0.4%
	2.2	PET Containers other than Beverage Containers	0.2%	0.2%
	2.3	Plastic MA Deposit Beverage Containers	0.3%	0.2%
	2.4	HDPE Bottles, colored and natural	0.1%	0.3%
	2.5	Plastic Tubs and lids	0.1%	0.2%
	2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.9%	0.8%
	2.7	Expanded Polystyrene Food Grade	0.2%	0.2%
	2.8	Expanded Polystyrene Non-food Grade	2.6%	4.5%
	2.9	Bulk Rigid Plastic Items	2.8%	4.9%
	2.1	Film (non-bag commercial and industrial packaging film)	3.8%	7.4%
	2.11	Grocery and other Merchandise Bags	0.1%	0.1%
	2.12	Other Film means plastic film	3.5%	2.1%
	2.13	Remainder/Composite Plastic	1.0%	1.0%

Table 3-5 Waste Composition of Roll-off Closed Top Continued				
WASTE CATEGORIES			Average	90% Confidence Level (+/-)
3.0 METALS	3.1	Aluminum Bev. Containers (non-MA deposit)	0.1%	0.1%
	3.2	Aluminum MA Deposit Beverage Containers	0.1%	0.1%
	3.3	Tin/Steel Containers	0.3%	0.4%
	3.4	Other Aluminum	0.2%	0.1%
	3.5	Other Ferrous and non-ferrous	0.2%	0.2%
	3.6	White Goods	0.0%	0.0%
	3.7	Remainder/Composite Metal	1.5%	1.7%
4.0 GLASS	4.1	Glass Bev. Containers (non-MA deposit)	0.6%	0.9%
	4.2	Other Glass Packaging Cont. (non-MA deposit)	0.2%	0.3%
	4.3	Glass MA Deposit Beverage Containers	0.2%	0.3%
	4.4	Remainder/Composite Glass	0.3%	0.5%
5.0 ORGANIC	5.1	Food Waste	6.0%	4.8%
	5.2	Branches and Stumps	0.0%	0.0%
	5.3	Prunings, Trimmings, Leaves and Grass	1.3%	2.7%
	5.4	Manures	0.0%	0.0%
	5.5	Remainder/Composite Organic	1.0%	0.8%
6.0 C & D	6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%
	6.2	Aggregates, Stone, Rock	0.0%	0.0%
	6.3	Wood – Treated	14.1%	21.1%
	6.4	Wood – untreated	11.3%	7.2%
	6.5	Asphalt Roofing	0.0%	0.0%
	6.6	Drywall/Gypsum Board (Identify if Chinese Drywall)	0.1%	0.1%
	6.7	Carpet and Carpet Padding	0.0%	0.0%
	6.8	Remainder/Composite Construction and Demolition	1.2%	1.9%
7.0 HHW	7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%
	7.2	Batteries – Lead Acid	0.0%	0.0%
	7.3	Batteries – Other	0.0%	0.0%
	7.4	Paint	1.8%	3.7%
	7.5	Bio-Hazardous	1.1%	1.5%
	7.6	Vehicle and Equipment Fluids	0.0%	0.0%
	7.7	Metal, Glass, and Plastic Cont.(cont. toxic materials)	0.1%	0.1%
	7.8	Pesticides and Fertilizers	0.0%	0.0%
	7.9	Other Hazardous or Household Hazardous Waste	0.0%	0.0%
8.0 ELET	8.1	Computer-related Electronics	0.7%	1.2%
	8.2	Other “brown goods”	0.3%	0.5%
	8.3	Televisions and Computer Monitors	0.0%	0.0%
9.0 OTHER	9.1	Tires and other rubber	0.4%	0.5%
	9.2	Textiles	2.4%	3.9%
	9.3	Bulky materials	0.0%	0.0%
	9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%
	10	OTHER MISCELLANEOUS	1.0%	0.9%

Table 3-6 Waste Composition of Roll-off Compactor

WASTE CATEGORIES			Average	90% Confidence Level (+/-)
1.0 PAPER	1.1	Uncoated Corrugated Cardboard/Kraft Paper	19.9%	6.1%
	1.2	Waxed Cardboard	4.2%	3.8%
	1.3	High Grade Office Paper	1.4%	0.9%
	1.4	Magazines/Catalogs	0.6%	0.7%
	1.5	Newsprint	0.7%	0.6%
	1.6	Other Recyclable Paper	2.2%	1.6%
	1.7	Compostable Paper	6.8%	2.9%
	1.8	Remainder/Composite Paper	2.3%	1.7%
2.0 PLASTICS	2.1	PET Beverage Containers	0.4%	0.2%
	2.2	PET Containers other than Beverage Containers	0.2%	0.1%
	2.3	Plastic MA Deposit Beverage Containers	0.2%	0.1%
	2.4	HDPE Bottles, colored and natural	0.2%	0.1%
	2.5	Plastic Tubs and lids	0.4%	0.1%
	2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.5%	0.2%
	2.7	Expanded Polystyrene Food Grade	0.2%	0.1%
	2.8	Expanded Polystyrene Non-food Grade	0.2%	0.1%
	2.9	Bulk Rigid Plastic Items	4.3%	3.1%
	2.11	Film (non-bag commercial and industrial packaging film)	2.5%	1.2%
	2.12	Grocery and other Merchandise Bags	0.3%	0.2%
	2.12	Other Film means plastic film	5.7%	1.9%
	2.13	Remainder/Composite Plastic	2.4%	2.1%
3.0 METALS	3.1	Aluminum Bev. Containers (non-MA deposit)	0.1%	0.1%
	3.2	Aluminum MA Deposit Beverage Containers	0.1%	0.0%
	3.3	Tin/Steel Containers	2.0%	2.9%
	3.4	Other Aluminum	0.2%	0.1%
	3.5	Other Ferrous and non-ferrous	0.9%	1.4%
	3.6	White Goods	0.0%	0.0%
	3.7	Remainder/Composite Metal	2.9%	3.6%
4.0 GLASS	4.1	Glass Bev. Containers (non-MA deposit)	0.4%	0.3%
	4.2	Other Glass Packaging Cont. (non-MA deposit)	0.1%	0.1%
	4.3	Glass MA Deposit Beverage Containers	0.2%	0.2%
	4.4	Remainder/Composite Glass	2.4%	4.2%
5.0 ORGANIC	5.1	Food Waste	22.1%	6.9%
	5.2	Branches and Stumps	0.0%	0.0%
	5.3	Prunings, Trimmings, Leaves and Grass	0.7%	0.6%
	5.4	Manures	0.0%	0.0%
	5.5	Remainder/Composite Organic	0.7%	0.6%

**Table 3-6 Waste Composition of Roll-off Compactor Continued**

WASTE CATEGORIES			Average	90% Confidence Level (+/-)
<b>6.0 C &amp; D</b>	6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%
	6.2	Aggregates, Stone, Rock	0.0%	0.1%
	6.3	Wood - Treated	4.5%	2.7%
	6.4	Wood - untreated	1.8%	1.8%
	6.5	Asphalt Roofing	0.0%	0.0%
	6.6	Drywall/Gypsum Board (Identify if Chinese Drywall)	0.4%	0.7%
	6.7	Carpet and Carpet Padding	0.0%	0.0%
	6.8	Remainder/Composite Construction and Demolition	0.2%	0.3%
<b>7.0 HHW</b>	7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%
	7.2	Batteries - Lead Acid	0.0%	0.0%
	7.3	Batteries - Other	0.0%	0.0%
	7.4	Paint	0.0%	0.1%
	7.5	Bio-Hazardous	0.3%	0.4%
	7.6	Vehicle and Equipment Fluids	0.0%	0.0%
	7.7	Metal, Glass, and Plastic Cont.(cont. toxic materials)	0.0%	0.0%
	7.8	Pesticides and Fertilizers	0.0%	0.0%
	7.9	Other Hazardous or Household Hazardous Waste	0.0%	0.0%
<b>8.0 Elett</b>	8.1	Computer-related Electronics	0.0%	0.0%
	8.2	Other "brown goods"	0.3%	0.3%
	8.3	Televisions and Computer Monitors	0.0%	0.0%
<b>9.0 OTHER</b>	9.1	Tires and other rubber	0.5%	0.5%
	9.2	Textiles	2.4%	2.0%
	9.3	Bulky materials	0.1%	0.1%
	9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%
	10	<b>OTHER MISCELLANEOUS</b>	1.4%	1.9%

**Table 3-7 Waste Composition of Rear Loader**

WASTE CATEGORIES			Average	90% Confidence Level (+/-)
<b>1.0 PAPER</b>	1.1	Uncoated Corrugated Cardboard/Kraft Paper	4.8%	1.2%
	1.2	Waxed Cardboard	0.1%	0.0%
	1.3	High Grade Office Paper	0.9%	0.4%
	1.4	Magazines/Catalogs	1.0%	0.2%
	1.5	Newsprint	1.3%	0.3%
	1.6	Other Recyclable Paper	3.3%	0.5%
	1.7	Compostable Paper	9.2%	0.8%
	1.8	Remainder/ Composite Paper	0.9%	0.1%
<b>2.0 PLASTICS</b>	2.1	PET Beverage Containers	0.5%	0.1%
	2.2	PET Containers other than Beverage Containers	0.2%	0.0%
	2.3	Plastic MA Deposit Beverage Containers	0.2%	0.1%
	2.4	HDPE Bottles, colored and natural	0.5%	0.1%
	2.5	Plastic Tubs and lids	0.5%	0.1%
	2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.7%	0.1%
	2.7	Expanded Polystyrene Food Grade	0.6%	0.1%
	2.8	Expanded Polystyrene Non-food Grade	0.1%	0.0%
	2.9	Bulk Rigid Plastic Items	2.7%	0.9%
	2.1	Film (non-bag commercial and industrial packaging film)	0.7%	0.2%
	2.11	Grocery and other Merchandise Bags	1.1%	0.2%
	2.12	Other Film means plastic film	4.3%	0.5%
	2.13	Remainder/ Composite Plastic	1.3%	0.2%

Table 3-7 Waste Composition of Rear Loader Continued

WASTE CATEGORIES			Average	90% Confidence Level (+/-)
<b>3.0 METALS</b>	3.1	Aluminum Bev. Containers (non-MA deposit)	0.1%	0.0%
	3.2	Aluminum MA Deposit Beverage Containers	0.1%	0.0%
	3.3	Tin/Steel Containers	0.5%	0.1%
	3.4	Other Aluminum	0.3%	0.1%
	3.5	Other Ferrous and non-ferrous	0.7%	0.4%
	3.6	White Goods	0.0%	0.0%
	3.7	Remainder/ Composite Metal	2.0%	0.7%
<b>4.0 GLASS</b>	4.1	Glass Bev. Containers (non-MA deposit)	0.7%	0.2%
	4.2	Other Glass Packaging Cont. (non-MA deposit)	0.4%	0.1%
	4.3	Glass MA Deposit Beverage Containers	0.4%	0.1%
	4.4	Remainder/ Composite Glass	0.3%	0.1%
<b>5.0 ORGANIC</b>	5.1	Food Waste	19.9%	1.9%
	5.2	Branches and Stumps	0.5%	0.4%
	5.3	Prunings, Trimmings, Leaves and Grass	6.7%	1.6%
	5.4	Manures	0.9%	0.5%
	5.5	Remainder/ Composite Organic	3.3%	0.7%
<b>6.0 C &amp; D</b>	6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%
	6.2	Aggregates, Stone, Rock	0.5%	0.4%
	6.3	Wood - Treated	5.1%	1.2%
	6.4	Wood - untreated	2.2%	0.8%
	6.5	Asphalt Roofing	0.0%	0.0%
	6.6	Drywall/ Gypsum Board (Identify if Chinese Drywall)	0.7%	0.4%
	6.7	Carpet and Carpet Padding	3.3%	1.1%
	6.8	Remainder/ Composite Construction and Demolition	2.0%	0.9%
<b>7.0 HHW</b>	7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%
	7.2	Batteries - Lead Acid	0.0%	0.0%
	7.3	Batteries - Other	0.1%	0.0%
	7.4	Paint	0.1%	0.2%
	7.5	Bio-Hazardous	2.4%	0.4%
	7.6	Vehicle and Equipment Fluids	0.1%	0.1%
	7.7	Metal, Glass, and Plastic Cont.(cont. toxic materials)	0.0%	0.0%
	7.8	Pesticides and Fertilizers	0.0%	0.0%
	7.9	Other Hazardous or Household Hazardous Waste	0.1%	0.0%
<b>8.0 ELET</b>	8.1	Computer-related Electronics	0.1%	0.1%
	8.2	Other "brown goods"	0.4%	0.2%
	8.3	Televisions and Computer Monitors	0.5%	0.4%
<b>9.0 OTHER</b>	9.1	Tires and other rubber	1.6%	0.6%
	9.2	Textiles	6.5%	1.1%
	9.3	Bulky materials	0.8%	0.6%
	9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%
	10	<b>OTHER MISCELLANEOUS</b>	1.5%	0.3%

Table 3-8 Waste Composition of Front Loader

WASTE CATEGORIES			Average	90% Confidence Level (+/-)
1.0 PAPER	1.1	Uncoated Corrugated Cardboard/Kraft Paper	11.2%	1.9%
	1.2	Waxed Cardboard	0.6%	0.7%
	1.3	High Grade Office Paper	1.4%	1.0%
	1.4	Magazines/Catalogs	1.0%	0.5%
	1.5	Newsprint	1.9%	1.1%
	1.6	Other Recyclable Paper	3.2%	1.1%
	1.7	Compostable Paper	7.1%	1.6%
	1.8	Remainder/ Composite Paper	1.8%	0.9%
2.0 PLASTICS	2.1	PET Beverage Containers	0.6%	0.2%
	2.2	PET Containers other than Beverage Containers	0.1%	0.1%
	2.3	Plastic MA Deposit Beverage Containers	0.2%	0.1%
	2.4	HDPE Bottles, colored and natural	0.4%	0.1%
	2.5	Plastic Tubs and lids	0.5%	0.2%
	2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.7%	0.2%
	2.7	Expanded Polystyrene Food Grade	0.8%	0.8%
	2.8	Expanded Polystyrene Non-food Grade	0.1%	0.1%
	2.9	Bulk Rigid Plastic Items	3.3%	1.4%
	2.1	Film (non-bag commercial and industrial packaging film)	1.2%	0.5%
	2.11	Grocery and other Merchandise Bags	0.6%	0.2%
	2.12	Other Film means plastic film	2.5%	0.5%
	2.13	Remainder/ Composite Plastic	1.3%	0.6%
3.0 METALS	3.1	Aluminum Bev. Containers (non-MA deposit)	0.1%	0.0%
	3.2	Aluminum MA Deposit Beverage Containers	0.1%	0.0%
	3.3	Tin/Steel Containers	0.5%	0.3%
	3.4	Other Aluminum	0.6%	0.4%
	3.5	Other Ferrous and non-ferrous	2.3%	1.6%
	3.6	White Goods	0.0%	0.0%
	3.7	Remainder/ Composite Metal	3.2%	1.8%
4.0 GLASS	4.1	Glass Bev. Containers (non-MA deposit)	0.4%	0.2%
	4.2	Other Glass Packaging Cont. (non-MA deposit)	0.3%	0.1%
	4.3	Glass MA Deposit Beverage Containers	0.3%	0.2%
	4.4	Remainder/ Composite Glass	0.3%	0.2%
5.0 ORGANIC	5.1	Food Waste	13.0%	2.2%
	5.2	Branches and Stumps	0.1%	0.3%
	5.3	Prunings, Trimmings, Leaves and Grass	4.0%	1.5%
	5.4	Manures	0.1%	0.1%
	5.5	Remainder/ Composite Organic	2.8%	1.4%
6.0 C & D	6.1	Asphalt Pavement, Brick, and Concrete	0.4%	0.5%
	6.2	Aggregates, Stone, Rock	0.1%	0.1%
	6.3	Wood - Treated	8.9%	3.5%
	6.4	Wood - untreated	3.2%	2.0%
	6.5	Asphalt Roofing	2.1%	2.3%
	6.6	Drywall/ Gypsum Board (Identify if Chinese Drywall)	0.8%	0.9%
	6.7	Carpet and Carpet Padding	3.3%	1.8%
	6.8	Remainder/ Composite Construction and Demolition	2.2%	1.5%

Table 3-8 Waste Composition of Front Loader Continued

WASTE CATEGORIES			Average	90% Confidence Level (+/-)
7.0 HHW	7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%
	7.2	Batteries – Lead Acid	0.1%	0.2%
	7.3	Batteries – Other	0.0%	0.0%
	7.4	Paint	0.5%	0.5%
	7.5	Bio-Hazardous	1.7%	0.6%
	7.6	Vehicle and Equipment Fluids	0.0%	0.0%
	7.7	Metal, Glass, and Plastic Cont.(cont. toxic materials)	0.0%	0.0%
	7.8	Pesticides and Fertilizers	0.0%	0.0%
	7.9	Other Hazardous or Household Hazardous Waste	0.1%	0.1%
8.0 ELETT	8.1	Computer-related Electronics	0.2%	0.2%
	8.2	Other “brown goods”	0.5%	0.3%
	8.3	Televisions and Computer Monitors	0.8%	0.8%
9.0 OTHER	9.1	Tires and other rubber	1.2%	0.9%
	9.2	Textiles	3.6%	1.1%
	9.3	Bulky materials	0.2%	0.2%
	9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%
	10	<b>OTHER MISCELLANEOUS</b>	1.8%	1.4%

Table 3-9 Waste Composition of Side Loader

WASTE CATEGORIES			Average	90% Confidence Level (+/-)
1.0 PAPER	1.1	Uncoated Corrugated Cardboard/Kraft Paper	2.1%	1.6%
	1.2	Waxed Cardboard	0.0%	0.0%
	1.3	High Grade Office Paper	0.3%	0.3%
	1.4	Magazines/Catalogs	1.4%	0.5%
	1.5	Newsprint	1.5%	0.9%
	1.6	Other Recyclable Paper	2.0%	0.9%
	1.7	Compostable Paper	11.3%	2.4%
	1.8	Remainder/Composite Paper	1.2%	0.5%
2.0 PLASTICS	2.1	PET Beverage Containers	0.5%	0.1%
	2.2	PET Containers other than Beverage Containers	0.3%	0.2%
	2.3	Plastic MA Deposit Beverage Containers	0.1%	0.1%
	2.4	HDPE Bottles, colored and natural	0.5%	0.2%
	2.5	Plastic Tubs and lids	0.6%	0.4%
	2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.4%	0.2%
	2.7	Expanded Polystyrene Food Grade	0.4%	0.2%
	2.8	Expanded Polystyrene Non-food Grade	0.2%	0.1%
	2.9	Bulk Rigid Plastic Items	3.3%	2.6%
	2.1	Film (non-bag commercial and industrial packaging film)	0.7%	1.1%
	2.11	Grocery and other Merchandise Bags	1.5%	0.8%
	2.12	Other Film means plastic film	4.5%	0.8%
	2.13	Remainder/Composite Plastic	2.7%	2.3%
3.0 METALS	3.1	Aluminum Bev. Containers (non-MA deposit)	0.1%	0.1%
	3.2	Aluminum MA Deposit Beverage Containers	0.1%	0.1%
	3.3	Tin/Steel Containers	0.6%	0.3%
	3.4	Other Aluminum	0.3%	0.1%
	3.5	Other Ferrous and non-ferrous	1.7%	1.5%
	3.6	White Goods	0.0%	0.0%
	3.7	Remainder/Composite Metal	1.7%	1.2%
4.0 GLASS	4.1	Glass Bev. Containers (non-MA deposit)	0.4%	0.4%
	4.2	Other Glass Packaging Cont. (non-MA deposit)	0.2%	0.3%
	4.3	Glass MA Deposit Beverage Containers	0.2%	0.2%
	4.4	Remainder/Composite Glass	0.6%	0.7%



**Table 3-9 Waste Composition of Side Loader Continued**

WASTE CATEGORIES			Average	90% Confidence Level (+/-)
<b>5.0 ORGANIC</b>	5.1	Food Waste	20.0%	3.7%
	5.2	Branches and Stumps	0.7%	1.2%
	5.3	Prunings, Trimmings, Leaves and Grass	5.5%	3.6%
	5.4	Manures	1.1%	1.1%
	5.5	Remainder/Composite Organic	3.6%	2.8%
<b>6.0 C &amp; D</b>	6.1	Asphalt Pavement, Brick, and Concrete	0.1%	0.1%
	6.2	Aggregates, Stone, Rock	2.9%	5.3%
	6.3	Wood - Treated	2.2%	3.1%
	6.4	Wood - untreated	2.3%	3.4%
	6.5	Asphalt Roofing	0.0%	0.0%
	6.6	Drywall/Gypsum Board (Identify if Chinese Drywall)	2.1%	1.9%
	6.7	Carpet and Carpet Padding	3.5%	3.8%
	6.8	Remainder/Composite Construction and Demolition	1.6%	2.5%
<b>7.0 HHW</b>	7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%
	7.2	Batteries - Lead Acid	0.0%	0.0%
	7.3	Batteries - Other	0.0%	0.0%
	7.4	Paint	0.0%	0.0%
	7.5	Bio-Hazardous	1.9%	1.1%
	7.6	Vehicle and Equipment Fluids	0.4%	0.7%
	7.7	Metal, Glass, and Plastic Cont.(cont. toxic materials)	0.1%	0.1%
	7.8	Pesticides and Fertilizers	0.3%	0.5%
	7.9	Other Hazardous or Household Hazardous Waste	0.1%	0.1%
<b>8.0 ELET</b>	8.1	Computer-related Electronics	0.1%	0.2%
	8.2	Other "brown goods"	0.9%	0.8%
	8.3	Televisions and Computer Monitors	0.0%	0.0%
<b>9.0 OTHER</b>	9.1	Tires and other rubber	1.6%	1.7%
	9.2	Textiles	7.2%	2.9%
	9.3	Bulky materials	0.0%	0.0%
	9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%
	10	<b>OTHER MISCELLANEOUS</b>	0.7%	0.7%

## 3.6 Observations and Analysis

### Fractions of Residential & ICI Sector Waste Streams

At the North Andover Facility, the Residential sector waste stream was estimated to be approximately 71% of the total and the ICI sector waste stream was estimated to be approximately 29% of the total. These numbers differ from those estimated by the MassDEP, which is a statewide average of 46% Residential waste and 54% ICI waste.

### Largest Overall Waste Categories

The largest waste categories, for the total waste stream (Residential and ICI sectors combined), were as follows:

Waste Category	Fraction of Total Waste Stream
Organic Material	28%
Paper	23%
Construction and Demolition	18%
Plastics	12%

The largest sub-categories, expressed as a fraction of the major categories, were as follows:

Waste Category	Sub-Categories
Organic Material	Food Waste: 57.6%
Paper	Compostable Paper: 30.9% Uncoated Corrugated Cardboard: 28.1%
Construction and Demolition	Wood – Treated: 28.4% Carpet/Carpet Padding: 25.4% Wood – Untreated: 22.7% Remainder/Composite C&D: 10.9%
Plastics	Other Film: 26.5% Bulk Rigid Plastic Items: 20.9% Remainder/Composite Plastic: 11.0% Film (non-bag commercial and industrial packaging film): 9.1% Plastic Containers Nos. 3, 4, 5, 6, 7: 8.8%

### Largest Residential Waste Categories

The largest residential waste categories, expressed as a fraction of the residential waste stream, were as follows:

Waste Category	Fraction of Residential Waste Stream
Organic Material	32.3%
Paper	20.1%
Construction & Demolition	17.2%
Plastics	11.2%

The sub-categories that contributed the highest percentages are reported in the table below. The sub-categories are reported as a fraction of their respective main category observed in the residential waste stream.

Waste Category	Sub-Categories
Organic Materials	Food Waste: 55.4%
Paper	Compostable Paper: 37.5% Uncoated Corrugated Cardboard/Kraft Paper: 23.0% Other Recyclable Paper: 19.4%
Construction & Demolition	Carpet & Carpet Padding: 28.8% Wood-Treated: 28.4% Wood – untreated: 21.2%
Plastics	Other Film: 28.8% Bulk Rigid Plastic Items: 18.7% Remainder/Composite Plastic: 10.3% Plastic Containers Nos. 3, 4, 5, 6, 7: 10.3%

### Largest ICI Waste Categories

The largest ICI waste categories, expressed as a fraction of the ICI waste stream, were as follows:

Waste Category	Fraction of ICI Waste Stream
Paper	29.6%
Construction and Demolition	19.7%
Organic Material	18.7%
Plastic	14.3%

The sub-categories that contributed the highest percentages are reported in the table below. The sub-categories are reported as a fraction of their respective main category observed in the ICI waste stream.

Waste Category	Sub-Categories
Paper	Uncoated Corrugated Cardboard: 36.6% Compostable Paper: 19.9%
Construction and Demolition	Wood – Treated: 28.5% Wood – Untreated: 25.9% Asphalt Roofing: 21.6% Carpet and carpet padding: 18.0%
Organic Materials	Food Waste: 66.5% Prunings, Trimmings, Leaves: 16.5% Remainder/Composite organics: 14.6%
Plastics	Bulk Rigid Plastic Items: 25.1% Other Film: 22.2% Remainder/Composite: 12.3%

## Section 4

# References

*ASTM D 5231-92 (Reapproved 2008), Standard Test Method for Determination of the Composition of Unprocessed Municipal Solid Waste.*

*MassDEP 2013 Class II Recycling Program, Waste Characterization Scope and Methodology Guidance.*

## Figures

---

Figure 1-1 Site Locus Map


Figure 1-2 Aerial Map

Figure 1-3 Tipping Floor Site Plan



FIG-1





# **BROWN AND CALDWELL**


151 Campanelli Drive, Suite B  
Middleborough, Massachusetts, 02346  
Tel. (508) 923-0879 Fax. (508) 923-0894

Note: USGS Quad Maps obtained from MassGIS scanned 5-CDset, dated July 1996. All other data from MassGIS Data Viewer software, updated May 2009.

## **FIGURE 1-1 SITE LOCUS MAP**

285 Holt Road  
N. Andover, Massachusetts

Prepared for:  
Wheelabrator N. Andover, Inc.



0 250 500 1,000  
Ft

Date: 10/13/2009

Project: 138138

Scale: 1" = 2000'

File: N. Andover  
Site Locus





# **BROWN AND CALDWELL**


151 Campanelli Drive, Suite B  
Middleborough, Massachusetts, 02346  
Tel. (508) 923-0879 Fax. (508) 923-0894

Note: USGS Quad Maps obtained from MassGIS scanned 5-CDset, dated July 1996. All other data from MassGIS Data Viewer software, updated May 2009.

## **FIGURE 1-2 AERIAL MAP**

285 Holt Road  
N. Andover, Massachusetts

Prepared for:  
Wheelabrator N. Andover, Inc.



0 250 500 1,000  
Ft


Date: 10/13/2009

Project: 138138

Scale: 1" = 1000'

File: N. Andover-Aerial





NOTE:  
1. EXISTING STRUCTURES SHOWN ON THIS PLAN ARE APPROXIMATE AND TO BE USED FOR ILLUSTRATION PURPOSES ONLY.

**BROWN AND  
CALDWELL**  
*151 Campanelli Drive, Suite B  
Middleborough, Massachusetts 02346  
Tel. (508) 923-0879 • Fax. (508) 923-0894*

DATE:	9/23/09
SCALE:	1"=60'
PROJECT:	143463
FILE:	N-Andover

<b>FIGURE 1-3 TIPPING FLOOR SITE PLAN</b>	
WHEELABRATOR NORTH ANDOVER, INC. 285 HOLT ROAD NORTH ANDOVER, MASSACHUSETTS 01845	
PREPARED FOR: WHEELABRATOR NORTH ANDOVER, INC.	



## Appendix A:

---

### Description of Waste Categories

## Description of Waste Categories

### PAPER

**Uncoated Corrugated Cardboard/Kraft Paper** means corrugated boxes or paper bags made from Kraft paper. Uncoated Corrugated Cardboard has a wavy center layer and is sandwiched between the two outer layers and does not have any wax coating on the inside or outside. Examples include entire cardboard containers, such as shipping and moving boxes, computer packaging cartons, and sheets and pieces of boxes and cartons. This type does not include chipboard. Examples of Kraft paper include paper grocery bags, un-soiled fast food bags, department store bags, and heavyweight sheets of Kraft packing paper.

**Waxed Cardboard** means cardboard with wax coating on the inside or outside.

**High Grade Office Paper** means the type of paper that is free of ground wood fibers; usually sulfite or sulphate paper; includes office printing and writing papers such as white ledger, color ledger, envelopes, and computer printout paper, bond, rag, or stationary grade paper. This subtype does not include fluorescent dyed paper or deep-tone dyed paper such as goldenrod colored paper.

**Magazines/Catalogs** means items made of glossy coated paper. This paper is usually slick, smooth to the touch, and reflects light. Examples include glossy magazines, catalogs, brochures, and pamphlets.

**Newsprint** means the class or kind of paper chiefly used for printing newspapers – i.e. uncoated ground-wood paper.

**Other Recyclable Paper** means paper, other than the paper mentioned above, which can be recycled. Examples include manila folders, manila envelopes, index cards, white envelopes, notebook paper, carbonless forms, junk mail, chipboard and uncoated paperboard, phone directories, non glossy catalogs, offshore cardboard and deep-toned or fluorescent dyed paper.

**Compostable Paper** means low grade paper that is not capable of being recycled, as well as food contaminated paper. Examples include paper towels, paper plates, waxed papers, egg cartons, pizza boxes, and tissues.

**Remainder/Composite Paper** means items made mostly of paper but combined with large amounts of other materials such as plastic, metal, glues, foil, and moisture. Examples include plastic coated corrugated cardboard, cellulose insulation, aseptic packages, polycoated (gable top) cartons, blueprints, sepia, onionskin, foiled lined fast food wrappers, frozen juice containers, carbon paper, self-adhesive notes, soft cover and hardcover books, and photographs.

### PLASTICS

**PET Beverage Containers (non-MA deposit containers)** means clear or colored PET beverage bottles other than MA deposit containers (water, flavored water, juice, sports drinks, etc.). When marked for identification, it bears the number 1 in the center of the triangular recycling symbol and may also bear the letters PETE or PET. A PET container usually has a small dot left from the manufacturing process, not a seam.

**PET Containers other than Beverage Containers (which originally contained non-hazardous material)** means types of containers such as PET jars, rectangular PET containers used for produce; egg cartons, etc.

**Plastic MA Deposit Beverage Containers** means plastic beverage containers subject to MA's bottle bill and marked as deposit containers in Massachusetts.

**HDPE Bottles, colored and natural, (which originally contained non-hazardous material)** means natural and colored HDPE containers. This plastic is usually either cloudy white, allowing light to pass through it

(natural) or a solid color, preventing light from passing through it (colored). When marked for identification, it bears the number —2 in the triangular recycling symbol and may also bear the letters — HDPE.

**Plastic Tubs and lids (HDPE, PP, etc)** Includes yogurt, margarine, sour cream, deli containers, etc. (i.e. injection molded).

**Plastic Containers #3-#7 (which originally contained non-hazardous material)** means plastic containers made of types of plastic other than HDPE or PET. Items may be made of PVC, PP, or PS. When marked for identification, these items may bear the number 3, 4, 5, 6, or 7 in the triangular recycling symbol. This subtype also includes unmarked plastic containers.

**Expanded Polystyrene Food Grade** means “Styrofoam” products includes food packaging and finished products made of expanded polystyrene including cups, plates, trays, clamshells, etc.

**Expanded Polystyrene Non-food Grade** includes non-food packaging and finished products made of expanded polystyrene including packing peanuts and other packaging materials.

**Bulk Rigid Plastic Items** means plastic objects other than disposable package items. These items are usually made to last for a few months up to many years. These include the plastics used in children toys, furniture, plastic landscape ties, buckets, crates, pallets, sporting goods, etc.

**Film (non-bag clean commercial and industrial packaging film)** means film plastic used for large-scale packaging or transport packaging. Examples include shrink-wrap, mattress bags, furniture wrap, and film bubble wrap.

**Grocery and other Merchandise Bags** means plastic shopping bags, used to contain merchandise to transport from the place of purchase, given out by the store with the purchase. Includes dry-cleaning plastic bags intended for one-time use and other plastic film commonly recycled with grocery bags.

**Other Film** means plastic film Examples include garbage bags and other types of plastic bags (sandwich bags, zipper-resealable bags, produce bags, frozen vegetable bags, newspaper bags), painting tarps, food wrappers such as candy-bar wrappers, mailing pouches, bank bags, X-ray film, metalized film (wine containers and balloons), and plastic food wrap.

**Remainder/Composite Plastic** means plastic that cannot be put in any other type or subtype. This type includes items made mostly of plastic but combined with other materials. Examples include auto parts made of plastic attached to metal, plastic drinking straws, foam packing blocks (not including expanded polystyrene blocks), plastic strapping, new plastic laminate (e.g., Formica), vinyl, linoleum, plastic lumber, imitation ceramics, handles and knobs, some kitchen ware, plastic string (as used for hay bales), and plastic rigid bubble/foil packaging (as for medications); CD's, and rigid plastic housewares, such as mop buckets, dishes, cups, and cutlery.

## METALS

**Aluminum Beverage Containers (non-MA deposit containers)** means beverage containers made from aluminum other than MA deposit containers.

**Aluminum MA Deposit Beverage Containers** means metal beverage containers subject to MA's bottle bill and marked as deposit containers in Massachusetts.

**Tin/Steel Containers** means rigid containers made mainly of steel, such as food and beverage containers. These items will stick to a magnet and may be tin-coated.

**Other Aluminum** – includes foil, food containers, aerosols (empty), etc.

**Other Ferrous and Non-Ferrous** means any iron or steel that is magnetic and metal items that are not magnetic (copper, brass, lead, zinc, etc). This subtype does not include "tin/steel containers". Examples

include empty or dry paint cans, structural steel beams, boilers, clothes hangers, pipes, some cookware, security bars, scrap ferrous/nonferrous items, and galvanized items such as nails and flashing.

**White Goods** means appliances that employ electricity, oil, natural gas, or liquefied propane and to preserve or cook food; wash or dry clothing, kitchen utensils, or related items; or to cool or heat air or water. These are primarily encased in metal, and include items such as refrigerators, freezers, stoves, water heaters, propane/compressed tanks, water coolers, dishwashers, clothes dryers, air conditioners, gas or electric ovens and ranges. White goods do not include microwaves.

**Remainder/Composite Metal** means metal that cannot be put in any other type. This type includes items made mostly of metal but combined with other materials and items made of both ferrous metal and nonferrous metal combined. Examples include microwaves, bikes, motors, insulated wire, and finished products that contain a mixture of metals, or metals and other materials, whose weight is derived significantly from the metal portion of its construction.

## GLASS

**Glass Beverage Containers (non-MA deposit containers)** includes wine bottles, nonalcoholic beverage containers, liquor bottles, etc.

**Other Glass Packaging Containers (non-MA deposit containers)** includes glass food and non-food containers such as sauces, jars, perfume containers, etc.

**Glass MA Deposit Beverage Containers** means glass beverage containers subject to MA's bottle bill and marked as deposit containers in Massachusetts.

**Remainder/Composite Glass** means glass that cannot be put in any other type. It may include items made mostly of glass but combined with other materials. Examples include Pyrex, Corning ware, crystal, plate glass, window and door glass, ceramics, porcelain, and other glass tableware, mirrors, non-fluorescent light bulbs, auto windshields, laminated glass, or any curved glass.

## ORGANIC MATERIALS

**Food Waste** means food material resulting from the processing, storage, preparation, cooking, handling, or consumption of food. This type includes material from industrial, commercial, or residential sources. Examples include discarded meat scraps, dairy products, eggshells, fruit or vegetable peels, and other food items from homes, stores and restaurants. This type includes apple pomace and other processed residues or material from canneries, wineries or other industrial sources.

**Branches and Stumps** means trees, stumps, branches, or other wood greater than 1 inch in diameter generated from landscapes, clearing land for commercial or residential development, road construction, agricultural land clearing, storms, or natural disaster.

**Prunings, Trimmings, Leaves and Grass** means plant material, except woody material 1 inch or less in diameter from any public or private landscapes. Examples include branches, prunings, shrubs, leaves, grass clippings, and plants. This subtype does not include woody material greater than 4 inches in diameter.

**Manures** means manure and soiled bedding materials from domestic, farm, wild, or ranch animals. Examples include manure and soiled bedding from animal production operations, racetracks, riding stables, animal hospitals, laboratories, zoos, nature centers, and other sources.

**Remainder/Composite Organic** means organic material that cannot be put in any other type or subtype. This type includes items made mostly of organic materials but combined with other materials. Examples include cork, hemp rope, hair, cigarette butts, full vacuum bags, sawdust, and animal feces.

## CONSTRUCTION AND DEMOLITION (IN THE MSW STREAM)

**Asphalt Pavement, Brick, and Concrete** includes asphalt pavement, brick, and concrete from construction activities and demolition of buildings, roads, and bridges and similar sources. Asphalt pavement also includes other black or brown, tar-like material mixed with aggregate and used as a paving material. Brick also includes masonry brick, landscaping or walkway brick. Concrete also includes pieces of building foundations, concrete paving, and cinder blocks.

**Aggregates, Stone, Rock** includes dirt, non-organic material from construction and landscaping activities. May also include products made predominately from these materials (i.e. granite counters).

**Wood – Treated** means wood that contains an adhesive, paint, stain, fire retardant, pesticide or preservative.

**Wood – Untreated** refers to any wood which does not contain an adhesive, paint, stain, fire retardant, pesticide or preservative; includes such items as pallets, skids, spools, packaging materials, bulky wood waste or scraps from newly built wood products. Does not including land clearing debris or yard waste prunings and trimmings.

**Asphalt Roofing** means composite shingles and other roofing material made with asphalt. Examples include asphalt shingles and attached roofing tar and tar paper.

**Drywall/Gypsum Board** means interior wall covering made of a sheet of gypsum sandwiched between paper layers. Examples include used or unused, broken or whole sheets of sheetrock, drywall, gypsum board, plasterboard, gypsum board, gyproc, and wallboard.

**Carpet and Carpet Padding** means flooring applications consisting of various natural or synthetic fibers which maybe bonded to some type of backing material and plastic, foam, felt, or other material used under carpet to provide insulation and padding.

**Remainder/Composite Construction and Demolition** means construction and demolition material that cannot be put in any other type or subtype. This type may include items from different types combined, which would be very hard to separate.

## HOUSEHOLD HAZARDOUS WASTE

**Ballasts, CFLs, and Other Fluorescents** include ballasts, which are devices that electrically control fluorescent light fixtures and that include a capacitor, CFLs, which are compact fluorescent bulbs, and other fluorescent lighting, which includes tubular fluorescent lamps, neon lamps, black lights, and other lamps used for sanitation or cosmetic purposes.

**Batteries – Lead Acid** means lead acid storage batteries most commonly used in vehicles such as cars, trucks, boats, etc.

**Batteries – Other** means alkaline (including alkaline rechargeable) or household batteries such as AA, AAA, C, D, 4.5 volt, button cell, rechargeable and 9 volt used for flashlights, small appliances, and electronic devices.

**Paint** means containers with paint in them. Examples include latex paint, oil based paint, and tubes of pigment or fine art paint. This type does not include dried paint, empty paint cans, or empty aerosol containers.

**Bio-Hazardous** - means discarded animal or human medical/treatment wastes including needles, first aid wastes, diapers and other products which are used in relation to animal or human care. This category does not include cat litter or animal feces.

**Vehicle and Equipment Fluids in containers and oil filters** means containers with fluids used in vehicles or engines. Examples include antifreeze, oil, and brake fluid. This type does not include empty vehicle and equipment fluid containers. Oil filters include vehicle engine oil filters.

**Empty Metal, Glass, and Plastic Containers (that originally contained toxic materials)** means all containers that are empty but that at one time contained toxic or hazardous fluids or other materials. Examples include empty antifreeze, oil, or lye containers.

**Pesticides and Fertilizers** means households and commercial products used to destroy or control organisms, pests or enhance plant growth.

**Other Hazardous or Household Hazardous Waste** means all household or commercial products characterized as toxic, corrosive, flammable, ignitable, radioactive, poisonous, or reactive.

## **ELECTRONICS**

**Computer-related Electronics** includes computer CPUs, laptop computers, notebook computers, processors, printers, scanners, keyboards, etc. This category does not include automated typewriters or typesetters, portable handheld calculators, portable digital assistants or other similar devices.

**Other “brown goods”** includes cell phones, I Pods, PDAs, small electronic appliances such as toasters, telephones, stereos, radios, clocks, hair dryers etc.

**Televisions and Computer Monitors** means a stand-alone display system containing a CRT or any other type of display primarily intended to receive video programming via broadcast. Examples also include non-CRT units such as plasma and LCD monitors.

## **OTHER MATERIALS**

**Tires and other rubber** means a continuous solid or pneumatic rubber covering intended for use on any type of vehicle (including bicycles), or trailer to be used in tandem with any type vehicle and other rubber products.

**Textiles** mean natural or man-made textile materials such as cottons, wools, silk, nylon, polyester. It includes clothing, curtains, towels and other fabric materials.

**Bulky Materials** means products made from multiple materials and large in size, which are meant for extended use. Includes mattresses, furniture (non-plastic), sinks, toilets, and other non-metal items.

**Restaurant Fats, Oils and Grease** means any fats, oils and grease generated from the food preparation process.

**Other Miscellaneous** means any other type of waste not listed in any other sort category.

## Appendix B:

---

### Waste Composition of Sample Loads for Season 1

Table B-1 First Season Waste Composition

Categories		Front Loader 1-1	Front Loader 1-2	Roll-off open top. 1-3	Rear Loader 1-4	Roll-off open top. 1-5	Roll-off open top. 1-6	Front Loader 1-7
1.0	PAPER							
1.1	Uncoated Corrugated Cardboard/Kraft Paper	7.1%	12.4%	5.3%	2.4%	7.4%	11.4%	10.3%
1.2	Waxed Cardboard	3.6%	2.4%	5.4%	4.5%	1.4%	2.6%	7.5%
1.3	High Grade Office Paper	0.6%	1.5%	0.5%	0.4%	0.8%	2.1%	1.6%
1.4	Magazines/Catalogs	0.0%	9.5%	16.7%	2.2%	4.1%	2.4%	2.3%
1.5	Newsprint	7.1%	9.8%	1.6%	3.4%	7.7%	0.3%	0.9%
1.6	Other Recyclable Paper	0.0%	0.7%	12.0%	2.1%	0.3%	1.2%	1.3%
1.7	Compostable Paper	20.7%	14.7%	0.4%	29.7%	6.6%	10.6%	20.3%
1.8	Remainder/Composite Paper	3.2%	1.0%	2.2%	4.8%	2.5%	2.4%	3.0%
2.0	PLASTICS							
2.1	PET Beverage Containers	0.6%	0.3%	0.2%	0.6%	0.5%	0.2%	1.3%
2.2	PET Containers other than Beverage Containers	0.8%	0.0%	0.2%	0.2%	0.0%	0.2%	0.0%
2.3	Plastic MA Deposit Beverage Containers	0.1%	0.8%	0.0%	0.4%	0.3%	0.2%	0.3%
2.4	HDPE Bottles, colored and natural	0.9%	0.9%	1.7%	1.0%	1.6%	1.1%	1.2%
2.5	Plastic Tubs and lids	1.7%	1.2%	1.0%	1.6%	1.0%	1.9%	1.3%
2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	2.6%	0.3%	0.3%	0.5%	0.2%	0.8%	0.0%
2.7	Expanded Polystyrene Food Grade	0.4%	0.3%	0.0%	0.9%	0.2%	0.4%	0.7%
2.8	Expanded Polystyrene Non-food Grade	0.5%	0.2%	0.3%	0.0%	0.0%	0.9%	0.0%
2.9	Bulk Rigid Plastic Items	2.8%	0.5%	1.2%	1.3%	0.2%	2.9%	1.1%
2.1	Film (non-bag commercial and industrial packaging film)	1.3%	1.4%	0.2%	3.0%	0.3%	0.5%	0.5%
2.11	Grocery and other Merchandise Bags	3.0%	1.0%	0.3%	1.6%	0.5%	0.3%	0.3%
2.12	Other Film means plastic film	6.3%	7.6%	1.9%	7.6%	3.3%	3.5%	9.7%
2.13	Remainder/Composite Plastic	3.4%	2.1%	4.4%	2.2%	4.8%	5.8%	3.3%
3.0	METALS							
3.1	Aluminum Beverage Containers (non-MA deposit)	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
3.2	Aluminum MA Deposit Beverage Containers	0.3%	0.4%	0.0%	0.2%	0.3%	0.2%	0.4%
3.3	Tin/Steel Containers	1.3%	0.6%	1.2%	0.6%	0.6%	1.0%	2.4%
3.4	Other Aluminum	0.1%	0.2%	0.4%	0.0%	1.1%	0.6%	0.2%
3.5	Other Ferrous and non-ferrous	0.3%	0.4%	1.5%	0.3%	19.6%	2.6%	1.1%
3.6	White Goods	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
3.7	Remainder Composite Metal	0.0%	0.9%	4.0%	0.0%	8.6%	3.2%	0.3%
4.0	GLASS							
4.1	Glass Beverage Containers (non-MA deposit containers)	1.2%	0.0%	0.9%	0.6%	1.3%	0.0%	2.0%
4.2	Other Glass Packaging Containers (non-MA deposit)	0.0%	0.6%	0.7%	0.5%	0.7%	1.2%	0.8%
4.3	Glass MA Deposit Beverage Containers	0.9%	0.0%	0.0%	0.4%	0.8%	1.3%	0.5%
4.4	Remainder/Composite Metal	0.4%	0.3%	6.4%	0.0%	0.0%	1.4%	0.0%
5.0	ORGANIC MATERIAL							
5.1	Food Waste	20.6%	3.0%	3.6%	11.4%	6.5%	10.4%	15.1%



Table B-1 First Season Waste Composition Continued

Categories		Front Loader 1-1	Front Loader 1-2	Roll-off open top. 1-3	Rear Loader 1-4	Roll-off open top. 1-5	Roll-off open top. 1-6	Front Loader 1-7
5.2	Branches and Stumps	0.0%	0.0%	0.0%	0.0%	6.1%	0.0%	0.0%
5.3	Prunings, Trimmings, Leaves and Grass	0.5%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
5.4	Manures	0.0%	0.0%	0.0%	4.6%	0.0%	0.0%	0.0%
5.5	Remainder/Composite Organic	0.0%	5.1%	0.0%	3.1%	0.0%	0.0%	0.0%
6.0	CONSTRUCTION AND DEMOLITION							
6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.2	Aggregates, Stone, Rock	1.4%	0.0%	0.0%	0.0%	2.3%	2.2%	2.9%
6.3	Wood – Treated	0.0%	3.9%	4.9%	0.3%	0.0%	2.0%	2.6%
6.4	Wood – untreated	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.5	Asphalt Roofing	0.0%	0.0%	0.0%	0.0%	0.0%	11.8%	0.0%
6.6	Drywall/Gypsum Board	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.7	Carpet and Carpet Padding	0.0%	2.2%	6.7%	0.0%	0.0%	0.0%	0.0%
6.8	Remainder/Compo-site Construction and Demolition	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.0	HOUSEHOLD HAZARDOUS WASTE							
7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%	0.2%	0.0%	0.0%	0.0%	0.0%
7.2	Batteries – Lead Acid	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.3	Batteries – Other	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.4	Paint	0.0%	0.0%	0.1%	0.0%	0.0%	0.0%	0.0%
7.5	Bio-Hazardous (Diapers)	5.3%	6.7%	0.0%	1.7%	2.8%	0.8%	1.2%
7.6	Vehicle and Equipment Fluids	0.0%	0.0%	0.3%	0.0%	0.0%	0.3%	0.0%
7.7	Empty Metal, Glass, and Plastic Containers (contained toxic materials)	0.0%	0.1%	0.8%	0.0%	0.3%	0.0%	0.0%
7.8	Pesticides and Fertilizers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.9	Other Hazardous or Household Hazardous Waste	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
8.0	ELECTRONICS							
8.1	Computer-related Electronics	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
8.2	Other “brown goods”	0.0%	0.0%	4.7%	0.2%	0.0%	0.5%	0.0%
8.3	Televisions and Computer Monitors	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
9.0	OTHER MATERIALS							
9.1	Tires and other rubber	0.0%	0.1%	0.0%	0.0%	0.0%	0.2%	0.0%
9.2	Textiles	1.0%	6.9%	7.9%	5.8%	5.5%	8.6%	3.7%
9.3	Bulky materials	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
10.0	OTHER MISCELLANEOUS	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%

Table B-2 First Season Waste Composition

Categories		Rear loader 1-8	Front loader 1-9	Rear loader 1-10	Roll-off comp. 1-11	Roll-off open top. 1-12	Rear loader 1-13	Front loader 1-14
1	PAPER							
1.1	Uncoated Corrugated Cardboard/Kraft Paper	4.4%	2.1%	3.4%	12.6%	8.4%	0.9%	2.6%
1.2	Waxed Cardboard	1.6%	6.5%	3.2%	2.9%	0.0%	4.2%	2.9%
1.3	High Grade Office Paper	1.0%	1.0%	0.5%	12.0%	3.7%	3.3%	2.3%
1.4	Magazines/Catalogs	1.6%	3.4%	3.1%	2.9%	0.7%	0.6%	1.5%
1.5	Newsprint	4.5%	1.5%	0.9%	0.6%	0.8%	1.0%	3.4%
1.6	Other Recyclable Paper	0.0%	0.5%	1.3%	8.2%	2.6%	0.2%	1.5%
1.7	Compostable Paper	19.8%	11.1%	9.0%	6.8%	3.3%	16.5%	10.5%
1.8	Remainder/Composite Paper	4.3%	2.7%	1.4%	0.1%	3.4%	3.8%	3.3%
2	PLASTICS							
2.1	PET Beverage Containers	1.5%	0.3%	0.5%	0.3%	2.7%	0.3%	1.7%
2.2	PET Containers other than Beverage Containers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
2.3	Plastic MA Deposit Beverage Containers	0.2%	0.2%	0.2%	0.1%	0.3%	0.1%	0.1%
2.4	HDPE Bottles, colored and natural	1.6%	1.7%	2.3%	0.7%	0.7%	1.2%	2.7%
2.5	Plastic Tubs and lids	1.3%	2.6%	1.3%	0.6%	1.0%	2.1%	2.3%
2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.0%	0.5%	0.0%	0.0%	0.2%	0.0%	0.0%
2.7	Expanded Polystyrene Food Grade	1.5%	0.7%	0.5%	0.1%	0.4%	1.1%	0.6%
2.8	Expanded Polystyrene Non-food Grade	0.0%	0.0%	0.1%	0.0%	0.0%	0.1%	0.0%
2.9	Bulk Rigid Plastic Items	0.3%	2.2%	0.0%	1.8%	1.0%	2.0%	1.0%
2.1	Film (non-bag commercial & industrial packaging film)	5.7%	0.1%	1.6%	23.2%	0.0%	0.1%	1.5%
2.11	Grocery and other Merchandise Bags	5.0%	2.1%	2.0%	0.1%	0.5%	2.9%	0.9%
2.12	Other Film means plastic film	15.3%	9.1%	13.3%	0.9%	4.5%	8.4%	4.8%
2.13	Remainder/Composite Plastic	3.8%	3.4%	4.8%	0.0%	4.0%	2.8%	3.3%
3	METALS							
3.1	Aluminum Beverage Containers (non-MA deposit)	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
3.2	Aluminum MA Deposit Beverage Containers	0.9%	0.2%	0.1%	0.2%	0.3%	0.2%	0.4%
3.3	Tin/Steel Containers	0.2%	1.1%	1.9%	0.2%	0.5%	0.6%	0.4%
3.4	Other Aluminum	2.9%	1.0%	0.5%	0.0%	0.1%	0.5%	6.6%
3.5	Other Ferrous and non-ferrous	0.0%	1.7%	0.1%	0.0%	7.8%	0.1%	1.2%
3.6	White Goods	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
3.7	Remainder Composite Metal	0.0%	0.0%	0.0%	3.6%	0.0%	0.0%	0.0%
4	GLASS							
4.1	Glass Beverage Containers (non-MA deposit)	1.0%	0.2%	0.8%	0.0%	0.7%	0.0%	0.0%
4.2	Other Glass Packaging Containers (non-MA deposit)	0.6%	0.0%	0.7%	0.0%	0.0%	0.0%	0.2%
4.3	Glass MA Deposit Beverage Containers	0.3%	0.0%	0.0%	0.0%	0.3%	0.2%	0.2%
4.4	Remainder/Composite Metal	0.0%	1.7%	0.9%	0.0%	0.0%	0.3%	0.0%
5	ORGANIC MATERIAL							
5.1	Food Waste	11.2%	14.0%	23.3%	0.0%	4.6%	20.0%	15.3%

Table B-2 First Season Waste Composition Continued

Categories		Rear loader 1-8	Front loader 1-9	Rear loader 1-10	Roll-off comp. 1-11	Roll-off open top. 1-12	Rear loader 1-13	Front loader 1-14
5.2	Branches and Stumps	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
5.3	Prunings, Trimmings, Leaves and Grass	0.0%	0.0%	0.3%	0.0%	0.0%	0.4%	0.3%
5.4	Manures	0.0%	4.7%	0.5%	0.0%	0.0%	4.4%	0.0%
5.5	Remainder/Composite Organic	0.0%	0.0%	0.0%	0.0%	0.0%	0.5%	0.0%
6	CONSTRUCTION AND DEMOLITION							
6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.2	Aggregates, Stone, Rock	1.7%	2.5%	2.7%	0.0%	0.0%	0.0%	0.0%
6.3	Wood – Treated	0.0%	0.0%	0.0%	0.6%	19.3%	0.2%	2.6%
6.4	Wood – untreated	0.3%	0.0%	0.6%	0.6%	23.0%	0.0%	2.2%
6.5	Asphalt Roofing	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.6	Drywall/Gypsum Board	0.0%	0.0%	0.0%	0.0%	3.3%	0.0%	7.3%
6.7	Carpet and Carpet Padding	0.7%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.8	Remainder/Compo-site Construction and Demolition	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7	HOUSEHOLD HAZARDOUS WASTE							
7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.2	Batteries – Lead Acid	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.3	Batteries – Other	0.0%	0.0%	0.0%	0.8%	0.0%	0.0%	0.0%
7.4	Paint	0.7%	0.0%	0.6%	0.0%	0.0%	0.0%	0.0%
7.5	Bio-Hazardous (Diapers)	3.4%	11.5%	15.3%	0.0%	0.0%	18.4%	4.7%
7.6	Vehicle and Equipment Fluids	0.0%	0.1%	0.0%	0.0%	0.0%	0.0%	0.2%
7.7	Empty Metal, Glass, and Plastic Containers (contained toxic materials)	0.0%	0.0%	0.0%	9.1%	0.0%	0.0%	0.0%
7.8	Pesticides and Fertilizers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.9	Other Hazardous or Household Hazardous Waste	0.0%	0.0%	0.0%	0.0%	0.0%	0.3%	0.0%
8	ELECTRONICS							
8.1	Computer-related Electronics	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
8.2	Other “brown goods”	0.0%	0.4%	1.0%	0.0%	0.0%	0.0%	0.9%
8.3	Televisions and Computer Monitors	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
9	OTHER MATERIALS							
9.1	Tires and other rubber	0.0%	0.0%	0.0%	0.0%	0.0%	0.9%	8.4%
9.2	Textiles	2.8%	9.3%	1.5%	0.2%	2.0%	1.6%	1.9%
9.3	Bulky materials	0.0%	0.0%	0.0%	10.5%	0.0%	0.0%	0.0%
9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
10	OTHER MISCELLANEOUS							
		0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%

**Table B-3 First Season Waste Composition**

Categories		Front loader 1-15	Rear loader 1-16	Front loader 1-17	Rear loader 1-18	Front loader 1-19	Front loader 1-20	Rear loader 1-21
1	PAPER							
1.1	Uncoated Corrugated Cardboard/Kraft Paper	2.8%	4.8%	11.9%	1.4%	3.9%	5.0%	1.2%
1.2	Waxed Cardboard	2.2%	3.1%	1.3%	3.1%	10.4%	1.3%	3.9%
1.3	High Grade Office Paper	2.4%	0.8%	2.6%	0.4%	1.1%	0.2%	0.3%
1.4	Magazines/Catalogs	0.7%	11.0%	0.6%	2.2%	0.0%	1.5%	1.0%
1.5	Newsprint	1.1%	4.9%	3.1%	1.7%	0.0%	0.3%	2.0%
1.6	Other Recyclable Paper	0.1%	0.0%	3.7%	3.9%	0.0%	1.9%	0.0%
1.7	Compostable Paper	15.8%	12.5%	9.2%	5.5%	18.4%	11.4%	7.7%
1.8	Remainder/Composite Paper	1.6%	2.7%	3.6%	8.0%	4.6%	2.3%	2.5%
2	PLASTICS							
2.1	PET Beverage Containers	0.3%	0.5%	0.9%	0.5%	2.3%	0.7%	0.8%
2.2	PET Containers other than Beverage Containers	0.1%	0.0%	0.0%	0.0%	0.7%	0.2%	0.0%
2.3	Plastic MA Deposit Beverage Containers	0.3%	0.2%	0.1%	0.1%	0.0%	0.4%	0.2%
2.4	HDPE Bottles, colored and natural	1.8%	1.8%	0.8%	1.9%	2.1%	1.2%	1.8%
2.5	Plastic Tubs and lids	2.6%	1.7%	0.9%	0.8%	4.8%	0.4%	0.7%
2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.3%	0.0%	0.0%	0.0%	0.7%	0.0%	0.2%
2.7	Expanded Polystyrene Food Grade	1.1%	0.8%	1.1%	1.4%	3.9%	0.4%	0.8%
2.8	Expanded Polystyrene Non-food Grade	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
2.9	Bulk Rigid Plastic Items	0.0%	2.4%	6.4%	0.0%	1.9%	2.2%	0.4%
2.1	Film (non-bag commercial & industrial packaging film)	1.6%	0.7%	1.1%	0.2%	0.0%	0.0%	0.1%
2.11	Grocery and other Merchandise Bags	2.0%	1.9%	0.8%	2.4%	6.4%	1.2%	11.8%
2.12	Other Film means plastic film	11.0%	6.0%	17.7%	12.1%	13.7%	4.2%	10.5%
2.13	Remainder/Composite Plastic	1.6%	1.8%	1.5%	2.6%	6.7%	0.3%	2.1%
3	METALS							
3.1	Aluminum Beverage Containers (non-MA deposit)	0.0%	0.1%	0.0%	0.1%	0.0%	0.0%	0.0%
3.2	Aluminum MA Deposit Beverage Containers	0.0%	0.2%	0.2%	0.2%	1.0%	0.2%	0.1%
3.3	Tin/Steel Containers	1.8%	0.9%	0.2%	1.4%	0.9%	0.2%	0.5%
3.4	Other Aluminum	1.2%	0.8%	0.2%	0.4%	0.6%	0.3%	0.5%
3.5	Other Ferrous and non-ferrous	1.2%	2.0%	5.2%	0.1%	0.0%	0.3%	0.0%
3.6	White Goods	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
3.7	Remainder Composite Metal	0.0%	0.0%	2.9%	0.0%	0.0%	0.0%	0.0%
4	GLASS							
4.1	Glass Beverage Containers (non-MA deposit)	0.0%	4.3%	0.0%	0.0%	0.4%	1.1%	0.0%
4.2	Other Glass Packaging Containers (non-MA deposit)	0.9%	1.2%	0.2%	0.3%	0.0%	0.0%	0.4%
4.3	Glass MA Deposit Beverage Containers	0.0%	0.5%	0.0%	0.0%	0.8%	0.0%	0.6%
4.4	Remainder/Composite Metal	0.5%	0.0%	0.0%	0.0%	0.0%	5.7%	0.2%

Table B-3 First Season Waste Composition Continued

Categories		Front loader	Rear loader	Front loader	Rear loader	Front loader	Front loader	Rear loader
		1-15	1-16	1-17	1-18	1-19	1-20	1-21
5	ORGANIC MATERIAL							
5.1	Food Waste	17.2%	11.1%	14.5%	31.5%	4.6%	4.9%	22.3%
5.2	Branches and Stumps	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
5.3	Prunings, Trimmings, Leaves and Grass	2.6%	6.7%	0.0%	0.2%	0.0%	0.0%	0.0%
5.4	Manures	2.0%	0.5%	0.0%	0.0%	7.9%	0.0%	0.0%
5.5	Remainder/Composite Organic	0.0%	0.5%	0.0%	0.0%	0.0%	0.0%	0.0%
6	CONSTRUCTION AND DEMOLITION							
6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.2	Aggregates, Stone, Rock	0.6%	1.8%	0.0%	0.0%	0.0%	31.8%	0.7%
6.3	Wood – Treated	0.8%	0.1%	0.0%	0.0%	0.0%	1.0%	1.2%
6.4	Wood – untreated	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.4%
6.5	Asphalt Roofing	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.6	Drywall/Gypsum Board	0.0%	0.0%	1.2%	0.0%	0.0%	0.0%	0.0%
6.7	Carpet and Carpet Padding	0.8%	1.9%	0.2%	0.0%	0.0%	0.0%	0.8%
6.8	Remainder/Compo-site Construction and Demolition	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7	HOUSEHOLD HAZARDOUS WASTE							
7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.2	Batteries – Lead Acid	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.3	Batteries – Other	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.4	Paint	0.0%	0.0%	0.0%	0.0%	0.0%	0.5%	0.0%
7.5	Bio-Hazardous (Diapers)	11.4%	4.0%	4.1%	15.5%	0.0%	1.6%	8.1%
7.6	Vehicle and Equipment Fluids	0.0%	0.0%	0.0%	0.0%	0.0%	0.5%	0.0%
7.7	Empty Metal, Glass, and Plastic Containers (contained toxic materials)	0.0%	0.0%	0.0%	0.0%	0.0%	0.3%	0.0%
7.8	Pesticides and Fertilizers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.9	Other Hazardous or Household Hazardous Waste	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
8	ELECTRONICS							
8.1	Computer-related Electronics	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	4.4%
8.2	Other “brown goods”	1.8%	0.0%	0.8%	0.0%	0.2%	0.0%	0.0%
8.3	Televisions and Computer Monitors	0.0%	0.0%	0.0%	0.0%	0.0%	12.4%	0.0%
9	OTHER MATERIALS							
9.1	Tires and other rubber	0.0%	0.0%	1.1%	0.0%	0.0%	0.0%	0.0%
9.2	Textiles	7.5%	5.7%	2.1%	2.2%	2.2%	3.9%	11.5%
9.3	Bulky materials	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
10	OTHER MISCELLANEOUS	0.0%	0.0%	0.0%	0.0%	0.0%	7.0%	0.0%

Table B-4 First Season Waste Composition

Categories		Front loader 1-22	Roll-off open top. 1-23	Front loader 1-24	Rear loader 1-25	Roll-off open top. 1-26	Front loader 1-27	Front loader 1-28
1	PAPER							
1.1	Uncoated Corrugated Cardboard/Kraft Paper	6.0%	3.4%	14.6%	18.7%	8.5%	7.7%	10.4%
1.2	Waxed Cardboard	3.5%	0.6%	4.4%	1.3%	5.4%	3.3%	2.6%
1.3	High Grade Office Paper	6.1%	1.0%	0.8%	0.0%	0.0%	1.3%	22.5%
1.4	Magazines/Catalogs	2.9%	0.0%	1.2%	0.0%	0.0%	0.8%	18.1%
1.5	Newsprint	1.3%	2.5%	2.9%	0.6%	0.0%	7.8%	2.4%
1.6	Other Recyclable Paper	0.0%	1.0%	0.0%	0.0%	0.0%	0.1%	0.0%
1.7	Compostable Paper	6.4%	10.6%	4.6%	10.9%	4.5%	8.5%	9.8%
1.8	Remainder/Composite Paper	3.9%	2.9%	1.3%	2.0%	1.7%	1.8%	2.6%
2	PLASTICS							
2.1	PET Beverage Containers	0.8%	0.1%	0.0%	0.2%	0.0%	0.5%	0.4%
2.2	PET Containers other than Beverage Containers	0.0%	0.0%	0.0%	0.6%	0.0%	0.0%	0.0%
2.3	Plastic MA Deposit Beverage Containers	0.1%	0.3%	0.2%	0.4%	0.1%	0.1%	0.5%
2.4	HDPE Bottles, colored and natural	2.6%	0.6%	0.4%	1.3%	0.0%	1.4%	0.9%
2.5	Plastic Tubs and lids	1.6%	0.2%	0.3%	0.7%	0.4%	1.3%	0.6%
2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
2.7	Expanded Polystyrene Food Grade	0.2%	0.1%	0.3%	0.1%	0.0%	0.4%	0.5%
2.8	Expanded Polystyrene Non-food Grade	1.5%	3.6%	0.0%	0.0%	1.8%	0.0%	0.1%
2.9	Bulk Rigid Plastic Items	2.9%	0.2%	0.5%	2.7%	11.1%	1.6%	1.5%
2.1	Film (non-bag commercial & industrial packaging film)	0.0%	0.0%	0.1%	0.0%	0.0%	0.0%	0.0%
2.11	Grocery and other Merchandise Bags	10.2%	2.3%	6.9%	4.4%	0.8%	2.3%	0.0%
2.12	Other Film means plastic film	17.4%	7.6%	7.6%	5.4%	3.6%	6.0%	5.3%
2.13	Remainder/Composite Plastic	2.5%	1.2%	1.2%	2.0%	11.2%	0.1%	2.1%
3	METALS							
3.1	Aluminum Beverage Containers (non-MA deposit)	0.2%	0.0%	0.0%	0.0%	0.0%	0.2%	0.1%
3.2	Aluminum MA Deposit Beverage Containers	0.0%	0.0%	0.0%	0.2%	0.0%	0.0%	0.3%
3.3	Tin/Steel Containers	0.8%	0.3%	0.3%	0.6%	0.0%	0.6%	0.0%
3.4	Other Aluminum	0.6%	0.3%	0.0%	0.0%	2.2%	1.6%	0.0%
3.5	Other Ferrous and non-ferrous	0.2%	0.1%	0.0%	0.2%	3.9%	3.0%	1.6%
3.6	White Goods	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
3.7	Remainder Composite Metal	1.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.1%
4	GLASS							
4.1	Glass Beverage Containers (non-MA deposit)	1.4%	1.0%	0.4%	0.0%	0.0%	0.3%	0.7%
4.2	Other Glass Packaging Containers (non-MA deposit)	0.9%	0.2%	0.0%	0.7%	0.0%	0.7%	0.0%

Table B-4 First Season Waste Composition Continued

Categories		Front loader 1-22	Roll-off open top. 1-23	Front loader 1-24	Rear loader 1-25	Roll-off open top. 1-26	Front loader 1-27	Front loader 1-28
4.3	Glass MA Deposit Beverage Containers	0.1%	0.0%	0.0%	0.3%	0.0%	0.0%	0.8%
4.4	Remainder/Composite Metal	0.9%	0.0%	0.5%	0.4%	0.0%	0.0%	1.7%
5	ORGANIC MATERIAL							
5.1	Food Waste	7.2%	1.0%	45.5%	27.3%	0.0%	3.3%	2.9%
5.2	Branches and Stumps	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
5.3	Prunings, Trimmings, Leaves and Grass	0.0%	0.0%	0.0%	3.9%	0.0%	23.2%	1.4%
5.4	Manures	1.4%	0.0%	0.0%	0.0%	0.0%	0.0%	1.7%
5.5	Remainder/Composite Organic	3.7%	3.0%	0.0%	0.0%	1.4%	0.1%	0.6%
6	CONSTRUCTION AND DEMOLITION							
6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.2	Aggregates, Stone, Rock	0.0%	53.5%	4.4%	0.0%	2.7%	1.8%	2.6%
6.3	Wood – Treated	5.3%	0.0%	0.0%	1.7%	0.3%	7.8%	3.9%
6.4	Wood – untreated	0.0%	0.2%	0.0%	0.0%	0.9%	1.1%	0.4%
6.5	Asphalt Roofing	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.6	Drywall/Gypsum Board	0.3%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.7	Carpet and Carpet Padding	0.0%	0.0%	0.0%	1.8%	4.3%	0.6%	0.0%
6.8	Remainder/Compo-site Construction and Demolition	0.0%	0.0%	0.0%	0.0%	15.2%	0.0%	0.0%
7	HOUSEHOLD HAZARDOUS WASTE							
7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.2	Batteries – Lead Acid	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.3	Batteries – Other	0.0%	0.0%	0.0%	0.0%	0.2%	0.0%	0.0%
7.4	Paint	0.0%	0.0%	0.0%	0.0%	0.0%	0.1%	0.0%
7.5	Bio-Hazardous (Diapers)	2.6%	0.0%	0.0%	10.6%	0.1%	3.7%	0.0%
7.6	Vehicle and Equipment Fluids	0.0%	0.0%	0.0%	0.1%	0.0%	0.1%	0.0%
7.7	Empty Metal, Glass, and Plastic Containers	0.0%	0.0%	0.0%	0.0%	0.0%	0.2%	0.3%
7.8	Pesticides and Fertilizers	0.0%	0.0%	0.0%	0.0%	5.0%	0.0%	0.0%
7.9	Other Hazardous or Household Hazardous Waste	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
8	ELECTRONICS							
8.1	Computer-related Electronics	0.0%	0.6%	0.0%	0.0%	1.4%	0.6%	0.0%
8.2	Other “brown goods”	0.5%	0.0%	0.0%	0.4%	0.0%	0.0%	0.0%
8.3	Televisions and Computer Monitors	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
9	OTHER MATERIALS							
9.1	Tires and other rubber	0.2%	0.0%	0.0%	0.0%	1.3%	0.0%	0.0%
9.2	Textiles	2.8%	1.5%	1.7%	0.5%	12.1%	5.8%	0.7%
9.3	Bulky materials	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
10	OTHER MISCELLANEOUS	2.3%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%

## Appendix C:

---

### Waste Composition of Sample Loads for Season 2



Table C-1 Second Season Waste Composition

Categories		Front Loader 2-01	Roll-Off Open Top 2-02	Front Loader 2-03	Rear Loader 2-04	Roll-Off Open Top 2-05	Front Loader 2-06	Front Loader 2-07
1	PAPER							
1.1	Uncoated Corrugated Cardboard/Kraft Paper	0.3%	0.0%	0.4%	1.3%	6.3%	23.9%	21.4%
1.2	Waxed Cardboard	0.0%	0.0%	0.1%	0.0%	0.0%	0.0%	0.0%
1.3	High Grade Office Paper	0.4%	0.0%	0.1%	0.6%	0.0%	0.1%	1.1%
1.4	Magazines/Catalogs	0.1%	0.0%	1.3%	0.8%	0.0%	0.0%	1.4%
1.5	Newsprint	0.0%	0.0%	7.0%	2.7%	0.0%	0.0%	2.6%
1.6	Other Recyclable Paper	9.2%	0.6%	2.8%	4.7%	0.0%	6.8%	6.0%
1.7	Compostable Paper	15.5%	0.2%	4.1%	5.7%	0.0%	2.9%	11.5%
1.8	Remainder/Composite Paper	1.1%	1.6%	0.3%	0.2%	0.0%	0.8%	0.3%
2	PLASTICS							
2.1	PET Beverage Containers	1.3%	0.1%	0.9%	0.1%	0.0%	0.8%	0.1%
2.2	PET Containers other than Beverage Containers	0.0%	0.0%	0.1%	0.1%	0.0%	0.2%	0.1%
2.3	Plastic MA Deposit Beverage Containers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
2.4	HDPE Bottles, colored and natural	0.3%	0.0%	0.5%	0.1%	0.0%	0.8%	24.2%
2.5	Plastic Tubs and lids	1.3%	0.0%	0.4%	0.4%	0.0%	0.7%	0.2%
2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.0%	0.0%	0.3%	0.2%	0.0%	0.1%	0.0%
2.7	Expanded Polystyrene Food Grade	3.0%	0.0%	0.8%	0.3%	0.0%	0.2%	0.0%
2.8	Expanded Polystyrene Non-food Grade	0.0%	0.0%	0.0%	0.2%	0.0%	0.0%	0.1%
2.9	Bulk Rigid Plastic Items	7.8%	0.0%	7.7%	8.6%	0.0%	0.0%	0.0%
2.1	Film (non-bag commercial & industrial packaging film)	0.0%	0.0%	6.1%	0.0%	6.5%	11.6%	3.9%
2.11	Grocery and other Merchandise Bags	0.1%	0.0%	0.0%	0.4%	0.0%	0.3%	0.1%
2.12	Other Film means plastic film	17.5%	0.2%	3.0%	1.6%	0.0%	1.6%	5.7%
2.13	Remainder/Composite Plastic	2.8%	0.1%	8.5%	0.6%	0.0%	1.5%	1.7%
3	METALS							
3.1	Aluminum Beverage Containers (non-MA deposit)	0.0%	0.2%	0.0%	0.0%	0.0%	0.0%	0.1%
3.2	Aluminum MA Deposit Beverage Containers	0.0%	0.0%	0.5%	0.0%	0.0%	0.0%	0.0%
3.3	Tin/Steel Containers	0.3%	0.0%	0.3%	0.2%	0.0%	0.8%	0.5%
3.4	Other Aluminum	0.1%	0.0%	0.0%	0.3%	38.7%	0.1%	0.0%
3.5	Other Ferrous and non-ferrous	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
3.6	White Goods	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
3.7	Remainder Composite Metal	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.1%
4	GLASS							
4.1	Glass Beverage Containers (non-MA deposit)	0.1%	14.1%	0.9%	0.0%	0.0%	0.0%	0.8%
4.2	Other Glass Packaging Containers (non-MA deposit)	0.0%	0.0%	0.0%	0.0%	0.0%	0.5%	0.0%
4.3	Glass MA Deposit Beverage Containers	0.0%	0.0%	0.0%	0.0%	0.0%	0.3%	0.0%
4.4	Remainder/Composite Metal	0.0%	0.0%	0.0%	0.0%	30.4%	0.0%	0.3%

Table C-1 Second Season Waste Composition Continued

Categories		Front Loader 2-01	Roll-Off Open Top 2-02	Front Loader 2-03	Rear Loader 2-04	Roll-Off Open Top 2-05	Front Loader 2-06	Front Loader 2-07
5	ORGANIC MATERIAL							
5.1	Food Waste	21.1%	0.0%	11.5%	20.3%	0.0%	13.3%	1.4%
5.2	Branches and Stumps	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
5.3	Prunings, Trimmings, Leaves and Grass	0.0%	0.0%	0.0%	20.4%	0.0%	0.0%	0.0%
5.4	Manures	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
5.5	Remainder/Composite Organic	3.6%	1.9%	0.5%	0.9%	0.0%	0.0%	0.3%
6	CONSTRUCTION AND DEMOLITION							
6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.2	Aggregates, Stone, Rock	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.3	Wood - Treated	0.0%	2.4%	28.7%	2.1%	0.0%	0.0%	3.5%
6.4	Wood - untreated	0.0%	0.0%	0.0%	0.0%	18.0%	12.8%	0.0%
6.5	Asphalt Roofing	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.6	Drywall/Gypsum Board	0.0%	0.0%	0.0%	0.0%	0.0%	1.0%	0.0%
6.7	Carpet and Carpet Padding	0.0%	0.0%	0.0%	7.2%	0.0%	0.0%	0.0%
6.8	Remainder/Compo-site Construction and Demolition	0.0%	24.0%	0.5%	0.0%	0.0%	0.0%	0.0%
7	HOUSEHOLD HAZARDOUS WASTE							
7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.2	Batteries - Lead Acid	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.3	Batteries - Other	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.4	Paint	0.0%	21.0%	0.0%	0.1%	0.0%	0.0%	0.2%
7.5	Bio-Hazardous (Diapers)	0.0%	0.0%	3.3%	2.3%	0.0%	0.2%	0.3%
7.6	Vehicle and Equipment Fluids	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.7	Empty Metal, Glass, and Plastic Containers	0.1%	0.0%	0.0%	0.0%	0.0%	0.0%	0.1%
7.8	Pesticides and Fertilizers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.9	Other Hazardous or Household Hazardous Waste	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
8	ELECTRONICS							
8.1	Computer-related Electronics	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.1%
8.2	Other "brown goods"	0.0%	0.0%	6.4%	0.6%	0.0%	0.0%	0.0%
8.3	Televisions and Computer Monitors	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
9	OTHER MATERIALS							
9.1	Tires and other rubber	4.7%	11.2%	1.0%	0.4%	0.0%	1.0%	2.4%
9.2	Textiles	5.4%	8.7%	0.2%	14.9%	0.0%	14.3%	9.0%
9.3	Bulky materials	0.0%	13.7%	0.0%	0.0%	0.0%	0.0%	0.0%
9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
10	OTHER MISCELLANEOUS	3.7%	0.0%	1.6%	1.4%	0.0%	3.3%	0.8%

Table C-2 Second Season Waste Composition

Categories		Rear Loader 2-08	Front Loader 2-09	Front Loader 2-10	Rear Loader 2-11	Front Loader 2-12	Rear Loader 2-13	Front Loader 2-14
1	PAPER							
1.1	Uncoated Corrugated Cardboard/Kraft Paper	3.1%	6.4%	3.0%	0.2%	9.5%	0.1%	3.2%
1.2	Waxed Cardboard	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
1.3	High Grade Office Paper	1.6%	0.6%	0.2%	0.0%	0.3%	9.5%	0.1%
1.4	Magazines/Catalogs	5.3%	1.1%	2.2%	4.0%	0.1%	0.6%	0.0%
1.5	Newsprint	6.9%	1.7%	2.0%	6.3%	1.0%	3.5%	0.0%
1.6	Other Recyclable Paper	7.1%	6.0%	6.3%	10.6%	5.4%	1.9%	3.7%
1.7	Compostable Paper	4.3%	2.9%	5.1%	9.8%	4.1%	15.0%	7.7%
1.8	Remainder/Composite Paper	0.9%	3.8%	2.3%	4.4%	1.0%	0.8%	1.9%
2	PLASTICS							
2.1	PET Beverage Containers	0.4%	0.5%	0.5%	0.7%	0.0%	0.4%	0.3%
2.2	PET Containers other than Beverage Containers	0.0%	0.4%	0.1%	0.3%	0.4%	0.1%	0.2%
2.3	Plastic MA Deposit Beverage Containers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
2.4	HDPE Bottles, colored and natural	0.2%	0.3%	0.6%	1.2%	0.2%	0.3%	0.1%
2.5	Plastic Tubs and lids	0.2%	0.3%	0.5%	0.4%	0.2%	0.1%	0.1%
2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.0%	0.0%	0.0%	0.0%	0.1%	0.3%	0.0%
2.7	Expanded Polystyrene Food Grade	0.5%	0.2%	0.2%	0.8%	0.1%	0.1%	0.6%
2.8	Expanded Polystyrene Non-food Grade	0.0%	0.0%	0.0%	0.0%	0.1%	0.0%	0.0%
2.9	Bulk Rigid Plastic Items	0.0%	0.0%	4.9%	0.0%	0.0%	0.2%	6.1%
2.1	Film (non-bag commercial and industrial packaging film)	0.2%	0.0%	0.1%	0.1%	0.0%	0.2%	0.0%
2.11	Grocery and other Merchandise Bags	0.3%	0.3%	0.4%	0.8%	0.5%	0.3%	0.3%
2.12	Other Film means plastic film	2.2%	2.2%	2.2%	3.0%	1.7%	0.7%	6.8%
2.13	Remainder/Composite Plastic	0.6%	1.1%	8.2%	1.4%	0.5%	7.0%	7.6%
3	METALS							
3.1	Aluminum Beverage Containers (non-MA deposit)	0.1%	0.0%	0.0%	0.0%	0.0%	0.2%	1.4%
3.2	Aluminum MA Deposit Beverage Containers	0.0%	0.1%	0.0%	0.0%	0.0%	0.0%	0.0%
3.3	Tin/Steel Containers	0.9%	1.2%	0.6%	1.6%	1.2%	1.2%	0.0%
3.4	Other Aluminum	0.1%	0.2%	0.3%	0.5%	0.3%	0.1%	1.2%
3.5	Other Ferrous and non-ferrous	0.0%	0.3%	0.0%	0.0%	0.2%	0.0%	0.0%
3.6	White Goods	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
3.7	Remainder Composite Metal	2.9%	1.4%	0.0%	0.0%	0.0%	0.3%	5.9%
4	GLASS							
4.1	Glass Beverage Containers (non-MA deposit)	1.0%	0.0%	0.0%	1.0%	1.6%	0.5%	3.3%
4.2	Other Glass Packaging Containers (non-MA deposit)	0.2%	0.2%	1.0%	0.1%	0.0%	0.0%	0.5%
4.3	Glass MA Deposit Beverage Containers	3.2%	0.2%	0.0%	0.2%	0.0%	0.0%	1.0%
4.4	Remainder/Composite Metal	0.0%	0.1%	0.0%	0.2%	0.4%	0.7%	0.0%

Table C-2 Second Season Waste Composition Continued

Categories		Rear Loader 2-08	Front Loader 2-09	Front Loader 2-10	Rear Loader 2-11	Front Loader 2-12	Rear Loader 2-13	Front Loader 2-14
5	ORGANIC MATERIAL							
5.1	Food Waste	6.0%	3.1%	9.7%	14.4%	9.6%	11.0%	7.7%
5.2	Branches and Stumps	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
5.3	Prunings, Trimmings, Leaves and Grass	12.3%	0.0%	0.0%	0.2%	7.6%	0.0%	0.0%
5.4	Manures	0.0%	0.0%	0.0%	3.2%	0.0%	0.0%	0.0%
5.5	Remainder/Composite Organic	3.1%	0.2%	2.4%	25.9%	2.0%	0.2%	0.3%
6	CONSTRUCTION AND DEMOLITION							
6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.2	Aggregates, Stone, Rock	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.3	Wood – Treated	0.0%	9.4%	0.3%	0.0%	0.0%	9.4%	6.3%
6.4	Wood – untreated	0.0%	23.7%	0.5%	0.0%	0.0%	0.7%	0.0%
6.5	Asphalt Roofing	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.6	Drywall/Gypsum Board	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.7	Carpet and Carpet Padding	8.8%	0.0%	11.5%	0.0%	12.6%	0.0%	0.0%
6.8	Remainder/Compo-site Construction and Demolition	0.0%	3.0%	0.6%	0.0%	0.0%	0.4%	0.0%
7	HOUSEHOLD HAZARDOUS WASTE							
7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.2	Batteries – Lead Acid	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.3	Batteries – Other	0.0%	0.0%	0.5%	0.1%	0.0%	0.0%	0.0%
7.4	Paint	0.0%	0.0%	2.5%	0.0%	0.0%	0.0%	0.0%
7.5	Bio-Hazardous (Diapers)	0.9%	0.6%	1.9%	4.8%	1.7%	0.8%	0.0%
7.6	Vehicle and Equipment Fluids	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.7	Empty Metal, Glass, and Plastic Containers (contained toxic materials)	0.0%	0.7%	1.5%	0.0%	0.0%	1.4%	0.0%
7.8	Pesticides and Fertilizers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.9	Other Hazardous or Household Hazardous Waste	0.1%	0.0%	0.0%	0.3%	0.2%	0.0%	0.0%
8	ELECTRONICS							
8.1	Computer-related Electronics	0.1%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
8.2	Other “brown goods”	6.5%	3.8%	0.0%	0.0%	4.1%	0.0%	0.0%
8.3	Televisions and Computer Monitors	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	19.2%
9	OTHER MATERIALS							
9.1	Tires and other rubber	0.2%	0.0%	3.3%	0.0%	1.5%	15.4%	11.9%
9.2	Textiles	1.3%	10.4%	15.3%	1.6%	22.5%	0.2%	1.4%
9.3	Bulky materials	17.7%	0.0%	8.0%	0.0%	0.0%	15.7%	0.0%
9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
10	OTHER MISCELLANEOUS	0.6%	13.4%	1.2%	1.9%	9.3%	0.8%	1.1%

Table C-3 Second Season Waste Composition

Categories		Roll Off Open Top 2-15	Rear Loader 2-16	Rear Loader 2-17	Rear Loader 2-18	Roll Off Open Top 2-19	Front Loader 2-20	Front Loader 2-21
1	PAPER							
1.1	Uncoated Corrugated Cardboard/Kraft Paper	5.9%	1.9%	8.8%	1.5%	0.0%	7.0%	17.1%
1.2	Waxed Cardboard	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
1.3	High Grade Office Paper	0.0%	0.0%	1.1%	0.6%	0.0%	0.0%	1.5%
1.4	Magazines/Catalogs	0.0%	0.7%	0.0%	0.7%	0.0%	4.7%	4.2%
1.5	Newsprint	0.0%	5.4%	0.0%	3.1%	0.0%	1.3%	0.7%
1.6	Other Recyclable Paper	0.0%	8.1%	4.0%	5.3%	0.0%	4.6%	11.3%
1.7	Compostable Paper	0.0%	11.8%	3.5%	4.8%	0.0%	5.2%	13.7%
1.8	Remainder/Composite Paper	0.0%	1.4%	1.2%	2.3%	0.0%	0.6%	1.6%
2	PLASTICS							
2.1	PET Beverage Containers	0.0%	0.3%	0.2%	0.2%	0.0%	0.7%	1.4%
2.2	PET Containers other than Beverage Containers	0.0%	0.1%	0.1%	0.1%	0.0%	0.1%	0.1%
2.3	Plastic MA Deposit Beverage Containers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.1%
2.4	HDPE Bottles, colored and natural	0.0%	0.4%	0.1%	0.1%	0.0%	0.3%	0.4%
2.5	Plastic Tubs and lids	0.0%	0.4%	0.0%	0.5%	0.0%	0.0%	0.0%
2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.0%	0.1%	0.1%	0.0%	0.0%	0.0%	0.0%
2.7	Expanded Polystyrene Food Grade	0.0%	1.1%	0.0%	0.4%	0.0%	0.4%	0.3%
2.8	Expanded Polystyrene Non-food Grade	0.0%	0.1%	0.0%	0.4%	0.0%	0.0%	0.0%
2.9	Bulk Rigid Plastic Items	0.0%	3.5%	13.9%	0.0%	0.0%	5.4%	0.0%
2.1	Film (non-bag commercial & industrial packaging film)	10.4%	0.0%	0.0%	0.0%	0.0%	0.3%	0.0%
2.11	Grocery and other Merchandise Bags	0.0%	0.9%	0.1%	0.6%	0.0%	0.4%	0.1%
2.12	Other Film means plastic film	0.0%	4.8%	1.3%	2.7%	0.0%	4.5%	3.7%
2.13	Remainder/Composite Plastic	0.0%	1.5%	5.9%	2.4%	100.0%	7.9%	6.5%
3	METALS							
3.1	Aluminum Beverage Containers (non-MA deposit)	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.4%
3.2	Aluminum MA Deposit Beverage Containers	0.0%	0.1%	0.0%	0.2%	0.0%	0.1%	0.5%
3.3	Tin/Steel Containers	0.0%	0.6%	0.0%	0.7%	0.0%	0.5%	0.0%
3.4	Other Aluminum	0.0%	0.6%	0.0%	0.5%	0.0%	0.0%	7.4%
3.5	Other Ferrous and non-ferrous	19.1%	0.0%	0.0%	1.2%	0.0%	2.0%	0.0%
3.6	White Goods	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
3.7	Remainder Composite Metal	0.0%	0.0%	7.5%	1.0%	0.0%	0.1%	0.0%
4	GLASS							
4.1	Glass Beverage Containers (non-MA deposit)	0.0%	0.0%	0.0%	0.8%	0.0%	0.0%	0.0%
4.2	Other Glass Packaging Containers (non-MA deposit)	0.0%	0.5%	0.0%	0.8%	0.0%	0.8%	0.0%
4.3	Glass MA Deposit Beverage Containers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
4.4	Remainder/Composite Metal	0.0%	0.0%	0.1%	1.9%	0.0%	0.1%	0.0%
5	ORGANIC MATERIAL							
5.1	Food Waste	0.0%	36.6%	2.6%	14.7%	0.0%	22.7%	19.3%

Table C-3 Second Season Waste Composition Continued

Categories		Roll Off Open Top 2-15	Rear Loader 2-16	Rear Loader 2-17	Rear Loader 2-18	Roll Off Open Top 2-19	Front Loader 2-20	Front Loader 2-21
5.2	Branches and Stumps	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
5.3	Prunings, Trimmings, Leaves and Grass	0.0%	0.0%	0.0%	8.1%	0.0%	0.0%	0.0%
5.4	Manures	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
5.5	Remainder/Composite Organic	0.0%	4.1%	0.8%	1.0%	0.0%	0.3%	1.1%
6	CONSTRUCTION AND DEMOLITION							
6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.2	Aggregates, Stone, Rock	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.3	Wood – Treated	17.9%	0.0%	0.0%	4.8%	0.0%	0.0%	0.0%
6.4	Wood – untreated	33.7%	0.0%	23.5%	5.1%	0.0%	1.0%	0.0%
6.5	Asphalt Roofing	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.6	Drywall/Gypsum Board	0.0%	0.0%	0.0%	0.0%	0.0%	1.9%	4.2%
6.7	Carpet and Carpet Padding	0.0%	0.0%	0.0%	9.5%	0.0%	6.4%	0.0%
6.8	Remainder/Compo-site Construction and Demolition	0.0%	0.0%	3.2%	0.0%	0.0%	7.5%	1.5%
7	HOUSEHOLD HAZARDOUS WASTE							
7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.2	Batteries – Lead Acid	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.3	Batteries – Other	0.0%	0.1%	0.0%	0.0%	0.0%	0.0%	0.0%
7.4	Paint	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.5	Bio-Hazardous (Diapers)	0.0%	5.4%	0.0%	1.4%	0.0%	0.2%	0.3%
7.6	Vehicle and Equipment Fluids	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.7	Empty Metal, Glass, and Plastic Containers	0.0%	0.0%	0.0%	0.2%	0.0%	0.0%	0.1%
7.8	Pesticides and Fertilizers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.9	Other Hazardous or Household Hazardous Waste	0.0%	0.1%	0.0%	0.1%	0.0%	0.0%	0.0%
8	ELECTRONICS							
8.1	Computer-related Electronics	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	1.2%
8.2	Other “brown goods”	0.0%	4.9%	11.5%	7.2%	0.0%	1.9%	0.0%
8.3	Televisions and Computer Monitors	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
9	OTHER MATERIALS							
9.1	Tires and other rubber	0.0%	0.2%	3.1%	6.1%	0.0%	0.5%	0.3%
9.2	Textiles	0.0%	2.0%	0.0%	8.0%	0.0%	9.0%	0.2%
9.3	Bulky materials	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
10	OTHER MISCELLANEOUS	13.0%	2.2%	7.1%	1.3%	0.0%	1.2%	0.9%

Table C-4 Second Season Waste Composition

Categories		Front Loader	Roll Off SC Compactor	Roll Off Open Top	Roll Off Open Top	Rear Loader	Front Loader
		2-23	2-24	2-25	2-26	2-27	2-28
<b>1</b>	<b>PAPER</b>						
1.1	Uncoated Corrugated Cardboard/Kraft Paper	7.7%	9.6%	3.9%	4.1%	1.0%	6.2%
1.2	Waxed Cardboard	0.0%	14.1%	0.0%	0.0%	0.0%	0.1%
1.3	High Grade Office Paper	0.5%	0.0%	0.0%	0.0%	0.1%	0.6%
1.4	Magazines/Catalogs	1.4%	0.0%	0.0%	0.0%	1.9%	0.6%
1.5	Newsprint	0.8%	2.2%	0.0%	0.0%	9.5%	1.3%
1.6	Other Recyclable Paper	3.6%	6.7%	0.0%	0.2%	19.0%	2.8%
1.7	Compostable Paper	4.4%	2.4%	0.0%	1.0%	2.3%	7.1%
1.8	Remainder/Composite Paper	0.6%	1.0%	0.0%	5.2%	9.7%	1.5%
<b>2</b>	<b>PLASTICS</b>						
2.1	PET Beverage Containers	0.8%	0.2%	0.0%	0.1%	0.4%	0.5%
2.2	PET Containers other than Beverage Containers	0.3%	0.2%	0.0%	0.1%	0.3%	0.1%
2.3	Plastic MA Deposit Beverage Containers	0.2%	0.7%	0.0%	0.0%	0.0%	0.1%
2.4	HDPE Bottles, colored and natural	0.4%	0.0%	0.0%	0.0%	0.5%	1.9%
2.5	Plastic Tubs and lids	0.3%	0.1%	0.0%	0.0%	0.1%	0.6%
2.6	Plastic Containers Nos. 3, 4, 5, 6, 7	0.1%	0.2%	0.0%	0.0%	0.1%	0.2%
2.7	Expanded Polystyrene Food Grade	0.4%	7.4%	0.0%	0.1%	0.0%	0.6%
2.8	Expanded Polystyrene Non-food Grade	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
2.9	Bulk Rigid Plastic Items	0.2%	0.0%	4.6%	5.9%	0.0%	6.0%
2.1	Film (non-bag commercial & industrial packaging film)	0.0%	2.0%	0.0%	0.0%	0.0%	0.0%
2.11	Grocery and other Merchandise Bags	0.8%	1.1%	0.0%	0.1%	0.2%	0.4%
2.12	Other Film means plastic film	1.9%	10.3%	0.0%	7.4%	1.4%	6.3%
2.13	Remainder/Composite Plastic	1.0%	0.4%	0.0%	0.1%	0.4%	1.7%
<b>3</b>	<b>METALS</b>						
3.1	Aluminum Beverage Containers (non-MA deposit)	0.0%	0.2%	0.0%	0.0%	0.3%	0.2%
3.2	Aluminum MA Deposit Beverage Containers	0.4%	0.2%	0.0%	0.6%	0.1%	0.2%
3.3	Tin/Steel Containers	1.5%	0.0%	0.0%	0.0%	0.1%	2.7%
3.4	Other Aluminum	0.2%	0.0%	0.0%	0.0%	0.0%	0.4%
3.5	Other Ferrous and non-ferrous	0.8%	0.0%	9.9%	0.0%	0.0%	0.0%
3.6	White Goods	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
3.7	Remainder Composite Metal	0.3%	0.0%	0.0%	0.0%	0.0%	1.6%
<b>4</b>	<b>GLASS</b>						
4.1	Glass Beverage Containers (non-MA deposit)	0.7%	1.4%	0.0%	0.0%	0.4%	5.7%
4.2	Other Glass Packaging Containers (non-MA deposit)	0.0%	0.0%	0.0%	0.0%	2.2%	0.5%
4.3	Glass MA Deposit Beverage Containers	0.0%	0.2%	0.0%	0.4%	0.0%	0.8%
4.4	Remainder/Composite Metal	0.4%	0.0%	0.0%	0.0%	0.0%	1.2%
<b>5</b>	<b>ORGANIC MATERIAL</b>						
5.1	Food Waste	22.7%	33.4%	0.0%	0.5%	4.3%	39.8%

Table C-4 Second Season Waste Composition Continued

Categories		Front Loader 2-23	Roll Off SC Compactor 2-24	Roll Off Open Top 2-25	Roll Off Open Top 2-26	Rear Loader 2-27	Front Loader 2-28
5.2	Branches and Stumps	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
5.3	Prunings, Trimmings, Leaves and Grass	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
5.4	Manures	0.5%	0.0%	0.0%	0.0%	0.0%	0.0%
5.5	Remainder/Composite Organic	6.1%	3.8%	0.0%	0.3%	0.3%	0.6%
6	CONSTRUCTION AND DEMOLITION						
6.1	Asphalt Pavement, Brick, and Concrete	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.2	Aggregates, Stone, Rock	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.3	Wood – Treated	2.4%	0.4%	9.6%	1.0%	0.0%	0.1%
6.4	Wood – untreated	24.5%	0.0%	6.7%	0.8%	0.0%	0.0%
6.5	Asphalt Roofing	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
6.6	Drywall/Gypsum Board	0.1%	0.0%	0.0%	50.8	0.0%	0.0%
6.7	Carpet and Carpet Padding	0.0%	0.0%	11.4%	0.0%	0.0%	0.0%
6.8	Remainder/Compo-site Construction and	1.0%	0.0%	0.0%	13.8	0.0%	0.0%
7	HOUSEHOLD HAZARDOUS WASTE						
7.1	Ballasts, CFLs, and Other Fluorescents	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.2	Batteries – Lead Acid	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.3	Batteries – Other	0.0%	0.1%	0.0%	0.0%	0.0%	0.0%
7.4	Paint	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.5	Bio-Hazardous (Diapers)	3.0%	0.2%	0.0%	0.0%	1.3%	1.0%
7.6	Vehicle and Equipment Fluids	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.7	Empty Metal, Glass, & Plastic Containers (contained toxic materials)	0.0%	0.0%	0.0%	0.1%	0.0%	0.0%
7.8	Pesticides and Fertilizers	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
7.9	Other Hazardous or Household Hazardous Waste	0.0%	0.0%	0.0%	0.0%	0.1%	0.2%
8	ELECTRONICS						
8.1	Computer-related Electronics	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
8.2	Other “brown goods”	0.0%	0.0%	9.0%	0.0%	1.0%	3.7%
8.3	Televisions and Computer Monitors	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
9	OTHER MATERIALS						
9.1	Tires and other rubber	0.0%	0.0%	0.0%	0.0%	0.0%	0.6%
9.2	Textiles	8.9%	0.9%	11.0%	0.0%	17.1%	0.6%
9.3	Bulky materials	0.0%	0.0%	33.9%	0.0%	25.0%	0.0%
9.4	Restaurant Fats, Oils and Grease	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
10	OTHER MISCELLANEOUS	1.2%	0.6%	0.0%	7.3%	1.0%	1.5%



## Appendix D:

---

### Driver Questionnaire and Field Data Sheet

## Driver Questionnaire

**Site:** \*Wheelabrator North Andover    \*Wheelabrator Millbury    \*Wheelabrator Saugus

**Date:** \_\_\_\_\_

**Time:** \_\_\_\_\_

**Truck ID No.** \_\_\_\_\_

**Hauler Company** \_\_\_\_\_

**Truck Type:** \*Dumpster    \*Front Loader    \*Rear Loader

\*Roll-off\_open top    \*Roll-off\_closed top    \*Roll-off\_compactor    \*Transfer Trailer

\*Other: \_\_\_\_\_

**Truck Weight:** lbs or Tons

Gross \_\_\_\_\_

Tare \_\_\_\_\_

Net \_\_\_\_\_

**Waste Type:**

\*Residential    \*Multifamily    \*School    \*Church    \*Office    \*Warehouse

\*Mall/Store    \*Factory    \*Hotel    \*Manufacturing Facility

\*Other: \_\_\_\_\_    \*Mixture: (Estimate Distribution) \_\_\_\_\_

Is your route scheduled:            Yes            No

How is it scheduled? \_\_\_\_\_

How many loads do you pick up per truck per day? \_\_\_\_\_

Are there contractual exclusions of certain waste material? \_\_\_\_\_

Was it raining today on your collection route?            Yes            No

Was there anything unusual or different about your route today? \_\_\_\_\_

\_\_\_\_\_

Sample Number \_\_\_\_\_

Date \_\_\_\_\_

2013 Wheelabrator WCS

Truck Type &amp; Number \_\_\_\_\_

Hauler Company \_\_\_\_\_

Site \_\_\_\_\_

WASTE CATEGORIES			1	2	3	4	5	6	TARE
1.0 PAPER	1.1	Uncoated Corrugated Cardboard/Kraft Paper							
	1.2	Waxed Cardboard							
	1.3	High Grade Office Paper							
	1.4	Magazines/Catalogs							
	1.5	Newsprint							
	1.6	Other Recyclable Paper							
	1.7	Compostable Paper							
	1.8	Remainder/Composite Paper							
2.0 PLASTICS	2.1	PET Beverage Containers							
	2.2	PET Containers other than Beverage Containers							
	2.3	Plastic MA Deposit Beverage Containers							
	2.4	HDPE Bottles, colored and natural							
	2.5	Plastic Tubs and lids							
	2.6	Plastic Containers Nos. 3, 4, 5, 6, 7							
	2.7	Expanded Polystyrene Food Grade							
	2.8	Expanded Polystyrene Non-food Grade							
	2.9	Bulk Rigid Plastic Items							
	2.10	Film (non-bag commercial and industrial packaging film)							
	2.11	Grocery and other Merchandise Bags							
	2.12	Other Film means plastic film							
	2.13	Remainder/Composite Plastic							
3.0 METALS	3.1	Aluminum Bev. Containers (non-MA deposit containers)							
	3.2	Aluminum MA Deposit Beverage Containers							
	3.3	Tin/Steel Containers							
	3.4	Other Aluminum							
	3.5	Other Ferrous and non-ferrous							
	3.6	White Goods							
	3.7	Remainder/Composite Metal							
4.0 GLASS	4.1	Glass Bev. Containers (non-MA deposit containers)							
	4.2	Other Glass Packaging Cont. (non-MA deposit)							
	4.3	Glass MA Deposit Beverage Containers							
	4.4	Remainder/Composite Glass							
5.0 ORGANIC	5.1	Food Waste							
	5.2	Branches and Stumps							
	5.3	Prunings, Trimings, Leaves and Grass							
	5.4	Manures							
	5.5	Remainder/Composite Organic							
6.0 C & D	6.1	Asphalt Pavement, Brick, and Concrete							
	6.2	Aggregates, Stone, Rock							
	6.3	Wood – Treated							
	6.4	Wood – untreated							
	6.5	Asphalt Roofing							
	6.6	Drywall/Gypsum Board (Identify if Chinese Drywall)							
	6.7	Carpet and Carpet Padding							
	6.8	Remainder/Composite Construction and Demolition							

Sample Number \_\_\_\_\_

Date \_\_\_\_\_

2013 Wheelabrator WCS

Truck Type &amp; Number \_\_\_\_\_

Hauler Company \_\_\_\_\_

Site \_\_\_\_\_

<b>7.0 HHW</b>	7.1	Ballasts, CFLs, and Other Fluorescents							
	7.2	Batteries – Lead Acid							
	7.3	Batteries – Other							
	7.4	Paint							
	7.5	Bio-Hazardous							
	7.6	Vehicle and Equipment Fluids							
	7.7	Metal, Glass, and Plastic Cont.(cont. toxic materials)							
	7.8	Pesticides and Fertilizers							
	7.9	Other Hazardous or Household Hazardous Waste							
<b>8.0 ELEC</b>	8.1	Computer-related Electronics							
	8.2	Other "brown goods"							
	8.3	Televisions and Computer Monitors							
<b>9.0 OTHER</b>	9.1	Tires and other rubber							
	9.2	Textiles							
	9.3	Bulky materials							
	9.4	Restaurant Fats, Oils and Grease							
	10.0	<b>OTHER MISCELLANEOUS</b>							

Bulky Items \_\_\_\_\_

## Appendix E:

---

### Permit Approval Class II Recycling Permit





COMMONWEALTH OF MASSACHUSETTS  
EXECUTIVE OFFICE OF ENERGY & ENVIRONMENTAL AFFAIRS  
**DEPARTMENT OF ENVIRONMENTAL PROTECTION**  
ONE WINTER STREET, BOSTON, MA 02108 617-292-5500

DEVAL L. PATRICK  
Governor

TIMOTHY P. MURRAY  
Lieutenant Governor

IAN A. BOWLES  
Secretary

LAURIE BURT  
Commissioner

September 25, 2009

Mr. Scott Emerson  
Wheelabrator North Andover, Inc.  
285 Holt Road  
North Andover, MA 01845

Re: Wheelabrator North Andover, Inc. BWP SW 16 Permit Modification Class II Recycling Program - Facility ID# 132771 – Final Permit

Dear Mr. Emerson:

Attached is Wheelabrator North Andover's Approved Class II Recycling Program permit modification under 310 CMR 19.300. MassDEP issued a Provisional Permit on August 26, 2009 pursuant to the provisions of Massachusetts General Laws (M.G.L.) Chapter 111, Section 150A and 310 CMR 19.000, and the "Solid Waste Management Facility Regulations". Pursuant to the provisions of 310 CMR 19.037 (4)(a), the MassDEP accepted written comments on this Permit for twenty-one (21) days from the date of issuance. Wheelabrator submitted several comments on the Provisional Permit and below is a summary of how MassDEP addressed these comments.

1. Wheelabrator indicated in its permit modification application and a subsequent e-mail correspondence during the Provisional Permit comment period that the data required for the Electronic Tracking System will be collected to the extent known and provided two specific examples, TIME\_OUT and HAULER\_ACCOUNT\_NUM, of data that may be difficult to collect. MassDEP amended Attachment 1 – Electronic Tracking System Data Specifications to reflect this under TIME\_OUT and HAULER\_ACCOUNT\_NUM. Any other changes in the Electronic Tracking System Data will need approval from MassDEP.
2. Wheelabrator commented that there are no provisions under Condition #11 (D) to allow for standard breaks and lunch. MassDEP amended this condition to allow for breaks in accordance with applicable law.

Other relevant changes to the Provisional Permit modification are listed below.

1. MassDEP added a condition (Condition #4) outlining MassDEP's right to inspect the facility.

2. An addition to Attachment 2 was made to include analysis by failed material in the Quarterly Comparative Analysis Report.
3. MassDEP amended Condition #12 extending the deadline for submitting a permittee's waste characterization methodology to no later than November 1, 2009, but maintained the deadline of January 1, 2010 for starting the waste characterization study.

MassDEP appreciates Wheelabrator's cooperation during the permitting process. If you have any additional questions, please contact me at 617-292-5988.

Sincerely,

Greg Cooper  
Deputy Division Director  
BWP - Consumer & Transportation Programs



COMMONWEALTH OF MASSACHUSETTS  
EXECUTIVE OFFICE OF ENERGY & ENVIRONMENTAL AFFAIRS  
**DEPARTMENT OF ENVIRONMENTAL PROTECTION**

ONE WINTER STREET, BOSTON, MA 02108 617-292-5500

DEVAL L. PATRICK  
Governor

TIMOTHY P. MURRAY  
Lieutenant Governor

IAN A. BOWLES  
Secretary

LAURIE BURT  
Commissioner

Final Decision Effective Date: September 25, 2009

Scott Emerson  
Wheelabrator North Andover, Inc.  
285 Holt Road  
North Andover, MA 01845

RE: PERMIT MODIFICATION APPROVAL- FINAL DECISION  
Application for: BWP SW 16  
CLASS II RECYCLING PROGRAM

AT: Wheelabrator North Andover, Inc.  
285 Holt Road  
North Andover, MA 01845  
Facility ID# 132771

Transmittal Number: X228985

Dear Mr. Emerson:

The Massachusetts Department of Environmental Protection, ("MassDEP"), has completed its review of the Permit Modification application ("Application") listed above in regard to participation in the Class II Recycling Program and determined the Application is administratively and technically complete. Accordingly, MassDEP approves this Application subject to the conditions contained herein effective on the date above.

**APPLICATION SUMMARY**

Permit Application: BWP SW 16 – Permit Modification - Class II Recycling Program  
Transmittal No.: X228985  
Applicant Name: Wheelabrator North Andover, Inc.  
Date: July 29, 2009  
Application Prepared By: Scott Emerson  
Wheelabrator North Andover, Inc.  
285 Holt Road  
North Andover, MA 01845  
Title of Submission: Class II Recycling Program Application



### **PROJECT BACKGROUND**

Wheelabrator North Andover owns and operates a municipal solid waste (MSW) combustion facility (the “Facility”) in North Andover, Ma. The Facility is permitted to combust 1,500 tons per day (TPD) of MSW. The Facility uses MSW as fuel and produces electricity. The Facility operates pursuant to permits issued by MassDEP, most notable the solid waste (310 CMR 19.000) and air quality (310 CMR 7.08(2)) regulations. The Facility was permitted and in operation prior to December 31, 1997.

### **PROJECT DESCRIPTION**

The Green Communities Act (Chapter 169 of the Acts of 2008) identifies a waste-to-energy facility in commercial operation prior to December 31, 1997 that uses conventional municipal solid waste technology to generate electricity as a Class II renewable energy generating source if it “operates or contracts for one or more recycling programs approved by the department of environmental protection.” MassDEP regulations at 310 CMR 19.300 et seq. require a solid waste facility permit modification for a waste-to-energy facility to qualify as a Waste Energy Generation Unit under the Department of Energy Resources Renewable Energy Portfolio Standards at 225 CMR 15.00.

### **APPROVAL AND CONDITIONS**

This Application complies with the requirements at 310 CMR 19.300 (Class II Recycling Program), 310 CMR 19.030(4) [permits] and 310 CMR 19.039 [request to modify permit] and was reviewed in accordance with 310 CMR 19.037 (Review Procedure for Permit Modifications, Permit Renewals, and other Approvals). The information contained in the application establishes that the facility complies with the criteria at 310 CMR 19.038(2)(a) 1-12 (Criteria for Review of Applications for a Permit or Permit Modifications).

This document is a permit issued pursuant to Massachusetts General Laws Chapter 111, Section 150A and 310 CMR 19.000, subject to the conditions set forth below. This permit does not convey property rights of any sort or any exclusive privilege.

1. Air Quality Regulations: The owner, operator and permittee shall comply with all applicable state (310 CMR 7.08(2) Air Pollution Control Regulations) and federal air pollution control regulations.
2. Solid Waste Regulations: The owner, operator and permittee shall comply with all applicable state regulations concerning solid waste facilities at 310 CMR 19.000.
3. Duration: This permit modification expires on October 1, 2014. To request a renewal of this permit, the permittee shall submit a BWP SW 16 permit modification application no later than 120 days prior to the date of expiration of this permit to avoid an interruption in qualification as a Waste Energy Generation Unit pursuant to 225 CMR 15.
4. Inspections: MassDEP reserves the right to inspect the Facility during normal working hours without due notice and/or require additional assessment(s) or action(s), including but not limited to modifying appropriate corrective measures in order to maintain the

environment free from objectionable nuisance conditions and/or dangers or threats to the public health or the environment.

5. Conditions of Permits and Authorizations: The owner, operator and permittee of the Facility shall comply with the provisions of 310 CMR 19.043, which standard conditions are already conditions of permittee's facility permit and are not modified by this permit decision in any way.
6. Permit Limitations: This permit modification is limited to the issues as described herein concerning the Class II Recycling Program and does not relieve the Facility and its owners and operators of the need to comply with all other applicable local, state or federal laws, regulations, permits and requirements.
7. Nothing in this permit decision shall modify any term, condition or requirement of the permittee's facility permit or other permits except as specifically set forth herein. If this permit modification approval conflicts with all or parts of prior permits, then this permit modification shall supersede the conflicting provisions of the prior permit approvals.
8. Electronic Tracking System: The permittee's electronic tracking system (described in 310 CMR 19.303) shall be capable of populating the fields and data values as indicated in Attachment 1 – Electronic Tracking System Data Specifications or as otherwise approved by MassDEP. The permittee shall have an electronic tracking system running and tracking all incoming loads at the Facility by October 1, 2009. The permittee shall populate the electronic tracking system for all incoming loads and all failed loads documented by the waste ban compliance professional and through the Facility's own waste ban compliance plan. The permittee shall revise or change the electronic tracking system as instructed by MassDEP to account for changes in the list of waste ban materials or other values deemed critical by MassDEP to ensure proper waste ban compliance information.
9. Reporting and Recordkeeping: The owner, operator and permittee of the Facility shall comply with the provisions of 310 CMR 19.303(4) [reporting] and 19.303(5) [recordkeeping].
10. Revenue from Sale of Attributes: In accordance with M.G.L. c. 25A, Section 11F(d) and 310 CMR 19.303(2)(b) and as indicated in the permittee's application, the permittee shall place 50% of the revenue from the sale of any RPS Class II Waste Energy Generation Attribute into the Sustainable Materials Recovery Program Expendable Trust no later than 30 days after the receipt of funds from any such sale. "Revenue" shall mean gross income not deducting any expenses.

11. Waste Ban Compliance Professional (WBCP):

- A. The permittee shall contract with an independent third party in accordance with 310 CMR 19.303(1)(c) to act as its WBCP by no later than October 1, 2009. The permittee shall send MassDEP evidence of this contract and the resume(s) of the independent third party contractor(s). Should the permittee need to contract with a different third party in the future, the permittee shall, in accordance with 310 CMR 19.039(6), submit a list of qualified independent third parties for MassDEP's approval with a BWP SW 45 permit application, at least 30 days prior to entering into a contract with a new independent third party.
- B. Attachment 2 – Quarterly Comparative Analysis Report is the report template that the permittee shall require the WBCP complete using the electronic tracking system and other relevant data when conducting the quarterly comparative analysis pursuant to 310 CMR 19.303(1)(c)(3). MassDEP reserves the right to modify this report template for subsequent quarters if necessary.
- C. The first quarter of inspections by the WBCP shall begin October 1, 2009 and end December 31, 2009. The permittee shall not allow any WBCP contracted by the permittee to begin monitoring incoming loads at the Facility until such WBCP has attended MassDEP's training for waste ban compliance professionals. MassDEP intends to hold such training no later than October 15, 2009. (Additional training for other WBCPs or permittee staff may be held at a later date.) Any new WBCP shall attend such training.
- D. The WBCP shall monitor all incoming loads for 10 inspection days every quarter, except those loads received by the facility during work breaks taken by the WBCP in accordance with applicable laws. Break periods will be documented by the WBCP and included in quarterly reports submitted to MassDEP. The WBCP's inspection days shall be determined using a random number generator application for selecting 10 dates from the planned operating days of the Facility for each quarter. The WBCP shall ensure that the permittee is not aware of the dates selected for inspection until the WBCP's arrival at the Facility but shall inform MassDEP's Regional Solid Waste Section Chief of the days selected for inspection at the beginning of each quarter. The permittee shall advise MassDEP if it learns of the dates that the WBCP will monitor incoming loads prior to his/her arrival at the Facility. The WBCP shall address routine conflicts between the days generated by the random number generator and the workdays of the WBCP (such as, but not limited to, vacation, holidays, sick or personal days) by using additional trained and contracted WBCPs. If the WBCP cannot otherwise conduct the inspection on the scheduled day due to Facility constraints, the WBCP shall select another day in the quarter using the random number generator application.

12. Waste Characterization Study: MassDEP finalized the waste characterization methodology guidance for all waste-to-energy facilities participating in the Class II Recycling Program on September 22, 2009. The permittee shall submit a waste characterization methodology based on MassDEP's guidance by no later than November 1, 2009. The permittee shall begin to conduct and perform its first waste characterization study beginning on or about January 1, 2010 or within 30 days of MassDEP's approval of



the Facility's waste characterization methodology, whichever is later. Subsequent waste characterization studies shall be conducted every 3 years thereafter. MassDEP may revise the waste characterization methodology for such subsequent studies at any time 120 days prior to the permittee conducting such study. Permittees shall submit a revised waste characterization methodology for MassDEP approval based on the revised guidance within 30 days of issuance of the revised guidance. The first waste characterization study report shall be submitted with the permittee's annual Facility report on February 15, 2011. If the waste characterization study report is not complete at the time the permittee's annual report is submitted to MassDEP, the permittee shall submit a status report of its waste characterization study with the appropriate facility annual report and submit a final waste characterization study report within 30 days after such status report.

#### **RIGHT TO APPEAL**

This approval has been issued pursuant to M.G.L. Chapter 111, Section 150A, and 310 CMR 19.037. Pursuant to 310 CMR 19.037(5), any person aggrieved by the issuance of this decision, except as provided for under 310 CMR 19.037(4)(b), may file an appeal for judicial review of said decision in accordance with the provisions of M.G.L. Chapter 111, Section 150A and M.G.L. Chapter 30A not later than thirty days following receipt. The standing of a person to file an appeal and the procedures for filing such appeal shall be governed by the provisions of M.G.L. c. 30A. Unless the person requesting an appeal requests and is granted a stay of the terms and conditions of the permit by a court of competent jurisdiction, the permit decision shall remain effective or become effective at the conclusion of the 30 day period.

#### **NOTICE OF APPEAL**

Any aggrieved person intending to appeal the decision to the superior court shall provide notice to MassDEP of the intention to commence such action. Said notice of intention shall include the MassDEP File Number X228985 and shall identify with particularity the issues and reason (s) why it is believed the approval decision was not proper. Such notice shall be provided to the Office of General Counsel and the Bureau of Waste Prevention. The appropriate addresses to send such notices are:

Office of General Counsel  
Department of Environmental Protection  
One Winter Street  
Boston, MA 02108

Assistant Commissioner  
Bureau of Waste Prevention  
Department of Environmental Protection  
One Winter Street  
Boston, MA 02108

No allegation shall be made in any judicial appeal of this decision unless the matter complained of was raised at the appropriate point in the administrative review procedures established in those regulations, provided that matter may be raised upon showing that it is material and that it was not reasonably possible with due diligence to have been raised during such procedures, or that

matter sought to be raised is of critical importance to the public health or environmental impact of the permitted activity.

If you have any questions or comments regarding this approval letter, feel free to contact me at 617-292-5988 or at the letterhead address.

Sincerely,

Greg Cooper  
Deputy Division Director  
BWP - Consumer & Transportation Programs

cc. John Carrigan, Solid Waste Section Chief, DEP/NERO  
Dr. Thomas Trowbridge, Chairman, North Andover Board of Health

## ATTACHMENT 1 – ELECTRONIC TRACKING SYSTEM DATA SPECIFICATIONS

Specification for electronic record source

### 1 Data Requirements

1.1 Data File Format – data recorded in the electronic tracking system must be made available to the MassDEP in comma separated value format, CSV.

1.2 Data Fields – data recorded in the electronic tracking system must meet the field names and data types, and be stored in the following order:

Field Order	Field Type	Field Name	Description	Data Format
1	F	FAC_NAME	Name of the solid waste facility where loads are observed	text
2	F	FAC_DATE	Date of Receipt	mm/dd/yyyy
3	F	SCALETICK_NUM	Scale House Ticket Number, also known as the Tare sheet, a receipt recording the vehicle's weight upon entering and departing the solid waste facility.	integer value number, #####
4	F	TIME_IN	Time of arrival at Facility	hh:mm:ss
5	F	TIME_OUT	Time of departure from Facility if recorded by scale	hh:mm:ss
6	F	HAULER_ACCT_NUM	Account number of the waste hauler delivering load or customer subcontracting to waste hauler	number
7	F	HAULER_NAME	Name of the waste hauler delivering load	text
8	F	TRUCK_TYPE	Description of the Truck Type delivering waste, to be assigned by the solid waste facility	text; values must include the following: "Roll-off - open top", "Roll-off - closed top", "Roll-off - compactor", "Rear loading packer", "Front loading packer", or "Transfer Trailer".
9	F	FAC_TRUCK_NUM	Number of the hauler vehicle, as assigned by the solid waste facility. This number usually is assigned for account management purposes such as billing.	number
10	F	FAC_TRAILER_NUM	Number of the container, if any, with materials being transported for disposal, as assigned by the solid waste facility	number
11	F	FAC_GEN	Name of the generator that has contracted for the disposal of materials, as identified by the facility, if available	text
12	F	FAC_GEN_ID	Customer number, if any, specified by facility	number
13	F	WASTE_TYPE	Type of waste delivered, to be assigned by the solid waste facility	text
14	F	WASTE_TON	Tonnage of waste delivered (short tons)	decimal

15	W	FAC_INSP_FNAME	First Name - either the Waste Ban Compliance Professional or Facility observer	text
16	W	FAC_INSP_LNAME	Last Name - either the Waste Ban Compliance Professional or Facility observer	text
17	W	HAUL_TRUCK_NUM	Number of the hauler vehicle, as assigned by the hauler dispatch location. This number is usually located on the front quarter panel, door, over the cab, and is the hauler's vehicle number on record	number
18	W	HAUL_CONTAIN_NUM	Number of the roll-off container (if any), with materials being transported for disposal, as assigned by the hauler dispatch location or container lessor	number
19	W	WB_BATT	Number of lead acid batteries observed in the load	count
20	W	WB_CRT	Number of CRTs observed in the load	count
21	W	WB_WHITEGOOD	Number of white goods observed in the load	count
22	W	WB_RECYC_PAPER	volume of paper or cardboard observed in the load, as a percentage of the total volume of the load  *note: field order number 28, "COMMENTS" contains provisions for clarification of values recorded in this field	percentage
23	W	WB_GMP_CONT	volume of Glass (G), Metal (M), and/or Plastic (P) containers observed in the load, as a percentage of the total volume of the load  *note: field order number 28, "COMMENTS" contains provisions for clarification of values recorded in this field	percentage
24	W	WB_LEAFYARD	volume of leaf and yard waste observed in the load, as a percentage of the total volume of the load	percentage
25	W	WB_ABCM	volume of asphalt pavement, brick, concrete, and metal observed in the load, as a percentage of the total volume of the load  *note: field order number 28, "COMMENTS" contains provisions for clarification of values recorded in this field	percentage
26	W	WB_PHOTOS	Number of pictures taken documenting the failed load, to be formatted as number.  ***Note: WBCP must record all pictures with a filename that must include first the value from the SCALETICK_NUM field (see above) and then the numerical order in which the photo was taken, separated by an hyphen, "-". e.g., SCALETICK_NUM 234567 was a failed load, and the WBCP took 4 pictures of that load. The WBCP would then save each picture as filenames 234567-1, 234567-2, 234567-3, 234567-4. The WBCP must provide a digital copy of all photos in a format to be approved by MassDEP  Failed loads observed through the Facility's Waste Ban Monitoring Plan need not include photos.	number

			<p>Comments: General comments, if any, with respect to the failed load observed.</p> <p>***Note: If a value is recorded in either field order number 22, 23 or 25, ("WB_RECYC_PAPER", "WB_GMP_CONT" or "WB_ABCM", respectively) the comments field must specify the predominant material observed for each field.</p> <p>For example, text saved in the "COMMENTS" field would indicate a failed load for 40% plastic containers and 10% glass containers as: Plastic. The percentage value in field "WB_GMP_CONT" in this example would be 50. The same rule applies to the fields, "WB_RECYC_PAPER" and "WB_ABCM".</p> <p>In cases with multiple reasons for failure, the predominant material for each field with percentage values recorded shall be specified.</p>	
27	W	COMMENTS		text

NOTE: Should MassDEP add new materials to the existing list of materials under 310 CMR 19.017 these materials types will be incorporated into the electronic tracking system and be documented accordingly.

## ATTACHMENT 2 – QUARTERLY COMPARATIVE ANALYSIS REPORT

This document describes the Comparative Analysis to be reported to the MassDEP pursuant to 310 CMR 19.300 for the first quarter of Waste Ban Compliance Professional Activity (October 1, 2009-December 31, 2009) and subsequent quarters unless otherwise modified by MassDEP.

A	B	C	D	E
1	Facility Name			
2	Date			
3	Prepared by			
4				
5	Total Loads			
6		<b>Total Number of Loads</b>	<b>Number of Failed Loads</b>	<b>%</b>
7	<b>Facility Waste Ban Compliance Plan Data</b>	Total number of loads received by the facility on days when the WBCP was not present	Number of failed loads observed by the on-going monitoring process observed on days when the WBCP was not present	=D7/C7
8	<b>Waste Ban Compliance Professional</b>	Total number of loads received by the facility on the 10 quarterly inspections when the WBCP was present	Number of failed loads observed by the WBCP	=D8/C8
9	<b>TOTAL</b>	=C7+C8 This will equal the total of all loads received by the facility during the reporting period	=D7+D8 This will equal the total number of failed loads received by the facility during the reporting period	
10	Note: please include a narrative with your report if necessary to explain the data			
11	Analysis by Truck Type			
12		<b>Total Number of Loads</b>	<b>Number of Failed Loads</b>	<b>%</b>
13	<b>Facility Waste Ban Compliance Plan Data</b>	[Note: all values in C14 through C20 should be a subset of C7]	[Note: all values in D14 through D20 should be a subset of D7]	
14	Roll-off open top			=D14/C14
15	Roll-off closed top			=D15/C15
16	Roll-off compactor			=D16/C16
17	Rear loading packer			=D17/C17
18	Front loading packer			=D18/C18
19	Transfer Trailer			=D19/C19
20	Unknown		[Note: this cell should always be zero. All observed failed loads should be classified by truck type]	



21	<b>TOTAL</b>	Sum of C14 thru C20. This total should be the same as C7	Sum of D14 thru D20. This total should be the same as D7	
22				
23	<b>Waste Ban Compliance Professional</b>	[Note: all values in C24 through C29 should be a subset of C8]	[Note: all values in D24 through D29 should be a subset of D8]	
24	Roll-off open top			=D24/C24
25	Roll-off closed top			=D25/C25
26	Roll-off compactor			=D26/C26
27	Rear loading packer			=D27/C27
28	Front loading packer			=D28/C28
29	Transfer Trailer			=D29/C29
30	Unknown		[Note: this cell should always be zero. All observed failed loads should be classified by truck type]	=D30/C30
31	<b>TOTAL</b>	Sum of C24 thru C29. This total should be the same as C8	Sum of D24 thru D29. This total should be the same as D8	
32				
33	<b>Analysis of Failed Loads by Material</b>			
34			<b>Number of Failed Loads</b>	<b>%</b>
35	<b>Facility Waste Ban Compliance Plan Data</b>		[Note: all values in D36 through D42 should be a subset of D7]	
36	Lead-acid Battery			=D36/C36
37	CRT			=D37/C37
38	White Good			=D38/C38
39	Paper (incl OCC)			=D39/C39
40	Containers (glass, plastic, metal)			=D40/C40
41	Leaf & Yardwaste			=D41/C41
42	C&D (incl asphalt, brick, concrete, C&D metal)			=D42/C42
43	<b>TOTAL</b>		Sum of D36 thru 426. This total should be the same as D7	
44				
45	<b>Waste Ban Compliance Professional</b>		[Note: all values in D46 through D52 should be a subset of D8]	
46	Lead-acid Battery			=D46/C46
47	CRT			=D47/C47
48	White Good			=D48/C48
49	Paper (incl OCC)			=D49/C49

50	Containers (glass, plastic, metal)			=D50/C50
51	Leaf & Yardwaste			=D51/C51
52	C&D (incl asphalt, brick, concrete, C&D metal)			=D52/C52
53	<b>TOTAL</b>		Sum of D46 thru D52. This total should be the same as D8	

## Appendix F:

---

### Calculation for Number of Samples

Date Checked	Checked By	Job Number	By	Date	Calc No.	Sheet No.
10/09/2009	J. Nissen	138138	H. Sfeir	10/05/2009	S1	1 of 4
<b>Project</b>			<b>Subject</b>			
Wheelabrator Waste Characterization Protocol			Calculation of number of samples			

### Objective:

Calculate the number of samples to achieve 90-percent (%) confidence level and 10-percent (%) precision.

### Methodology:

The number of samples was calculated using ASTM D5231-92 (2008) for a typical sample size of 200 to 300 lb (91 to 136 kg).

Therefore, the number of sorting samples (One sample per vehicle loads) ( $n$ ) required to achieve a desired level of measurement precision is a function of the component(s) under consideration and the confidence level. The governing equation for  $n$  is as follows:

$$n = (t^* s / e \cdot \bar{x})^2 \quad (1)$$

Where:

$t^*$  = student  $t$  statistic corresponding to the desired level of confidence,  
 $s$  = estimated standard deviation,  
 $e$  = desired level of precision, and  
 $\bar{x}$  = estimated mean,

All numerical values for the symbols are in decimal notation so for a precision value ( $e$ ) of 10 %, 0.1 was used.

For one sorting sample per vehicle load and for corrugated cardboard as the selected governing component:

$$\begin{aligned}
 t^*(n=\infty) &= 1.645 \text{ (from table 4)} \\
 s &= 0.06 \text{ (from table 3)} \\
 e &= 0.10 \text{ (or 10\%)} \\
 \bar{x} &= 0.14 \text{ (from table 3)}
 \end{aligned}$$

As required by MassDEP Waste Characterization Protocol at 90% confidence level and 10% precision the number of samples calculated using equation (1)

$$n = \left[ \frac{1.645(0.06)}{0.1(0.14)} \right]^2 = 50 \quad \text{Therefore, } n_o = 50$$

Date Checked	Checked By	Job Number	By	Date	Calc No.	Sheet No.
10/09/2009	J. Nissen	138138	H. Sfeir	10/05/2009	S1	2 of 4
<b>Project</b>			<b>Subject</b>			
Wheelabrator Waste Characterization Protocol			Calculation of number of samples			

Referring again to Table 4, for n=50

$$t_{*90}(n=50)=1.677$$

$$n = \left[ \frac{1.677(0.06)}{0.1(0.14)} \right]^2 = 52 \quad 52=n'$$

**Table 3 Values of Mean ( $\bar{x}$ ) and Standard Deviation ( $s$ ) for Within-Week Sampling to Determine MSW Component Composition<sup>A</sup>**

Component	Standard Deviation (s)	Mean ( $\bar{x}$ )
Mixed Paper	0.05	0.22
Newsprint	0.07	0.10
Corrugated	0.06	0.14
Plastic	0.03	0.09
Yard waste	0.14	0.04
Food waste	0.03	0.10
Wood	0.06	0.06
Other organics	0.06	0.05
Ferrous	0.03	0.05
Aluminum	0.004	0.01
Glass	0.05	0.08
Other inorganic	0.03	0.06
Total		1.00

<sup>A</sup>. The tabulated mean values and standard deviations are estimates based on field test data reported for MSW sampled during weekly sampling periods at several locations around the United States.

Date Checked	Checked By	Job Number	By	Date	Calc No.	Sheet No.
10/09/2009	J. Nissen	138138	H. Sfeir	10/05/2009	S1	3 of 4

Project	Subject
Wheelabrator Waste Characterization Protocol	Calculation of number of samples

Table 4 Values of t Statistics ( $t^*$ ) as a Function of Number of samples and Confidence Interval

Number of Samples, $n$	90
2	6.314
3	2.920
4	2.353
5	2.132
6	2.015
7	1.943
8	1.895
9	1.860
10	1.833
11	1.812
12	1.796
13	1.782
14	1.771
15	1.761
16	1.753
17	1.746
18	1.740
19	1.734
20	1.729
21	1.725
22	1.721
23	1.717
24	1.714
25	1.711
26	1.708
27	1.706
28	1.703
29	1.701
30	1.699
31	1.697
36	1.690
41	1.684
46	1.679
51	1.676
61	1.671
71	1.667
81	1.664
91	1.662
101	1.660
121	1.658
141	1.656
161	1.654
189	1.653
201	1.653
$\infty$	1.645



Date Checked	Checked By	Job Number	By	Date	Calc No.	Sheet No.
10/9/2009	J. Nissen	138138	H. Sfeir	10/05/2009	S1	4 of 4

Project	Subject
Wheelabrator Waste Characterization Protocol	Calculation of number of samples

### Results:

Since 52 (that is,  $n'$ ) is within 10 % of 50 (that is,  $n$ ), 52 samples should be selected for analysis to provide 90% confidence level.

Similar calculations was performed for the following recyclable waste components and the results of the calculations are listed Table A-1.

Table A-1 Number of samples required for sorting at 90% confidence level.

Component	Standard Deviation ( $s$ )	Mean ( $\bar{x}$ )	Number of Samples, $n$ at 90% confidence level	Number of Samples, $n'$ at 90% confidence level and 10% precision
Mixed paper	0.05	0.22	14	16
Corrugated Cardboard	0.06	0.14	50	52
Plastic	0.03	0.09	30	32
Food waste	0.03	0.10	24	26
Aluminum	0.004	0.01	43	45